Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

City of Jacksonville, Florida
Procurement Award Form (PAF)

Part 1: Form Type JPAC Award Request and Administrative Details

Goods and/or Services: Emergency Hurricane Season Storm Sewer Cave-In Repair - CS-0078-24

Requested Action/Authority:

Recommendation to Award

Justification/Explanation:

Jax Utilities Management submitted the lowest responsive qualified bid in the amount of $1,285,272.32.

Legal Contract #:	N/A	Contract Date:	08/08/2024	Change Order/AMD #:	N/A	
PO/Release #:	N/A	Bid Date:	07/07/2024	Awarded Supplier:	JaxUtilities Management Inc.	
Licenses Verified:	Yes	Effective Date:	08/08/2024	Basis of Award:	LPTA	
Federally Funded:	Yes	No. Invited:	6	Responses Received:	2	Attachments:
Solicitation:	N/A - 0078 - 24			Procurement Contract #:	N/A - N/A	
Executed By:	Office of General Counsel					

PoP:Base:	3 years	Options:	One (1} Two (2} year Renewal Option	Extension(s):	1
JSEB Rec.:	Participation	%:	40	Bonds Waived Pursuant To:	N/A

Fund:	00000	Center:	000000	Acct:	000000	Proj:	00000000	Activity:	0000000000	$	1,285,272.32
Fund:		Center:		Acct:		Proj:		Activity:		$	
Fund:		Center:		Acct:		Proj:		Activity:		$	

New NTE/GMP:	$ 1,285,272.32	Contingent Amount:	$ 0.00	DMP/ODPO Amount:	$ 0.00

Using Agency/BU:	PWGM:R-O-W_AND_STORMWATER_MAINTENANCE			
Concurrence:	Signed by: Carroll, James 6CE565F613434A4...	Title:	CHIEF OF RIGHT OF WAY AND STORMWATER MAINTENANCE	7/31/2024
Concurrence:	DocuSigned by: Nina Sicker 1EFA223D5D23487...	Title:	DIRECTOR OF PUBLIC WORKS	8/7/2024
Concurrence:		Title:		
Concurrence:		Title:		

Procurement Analyst/Buyer:	Signed by: David Klages 2E820995264D4AE...	Chief of Procurement:	DocuSigned by: B19F1D517352456...
Name:	David Klages	Name:	Dustin L. Freeman

Initial DT

Initial DT

Part 2: JPAC Actions on Above Requests/Recommendations
All Award Actions Subject to Lawfully Appropriated Funds

Members Who Approve:	
Members Who Disapprove:	
Other Action:	

Date:

Part 3: Final Awarding Authority Action

Action:

Date:

Signature:

Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

PAF Instructions

Form Type: Select the type of award from the dropdown options. This form will be used for all Procurement awards (Administrative Awards and JPAC Requests).

Goods and/or Services: Enter a brief description of the types of goods and services included in the request.

Requested Action/Authority: Enter a brief description of the requested action or authority being sought. i.e.; *request permission to award to the lowest, responsive responsible bidder for ITB or award the highest ranked supplier for an RFP*.

Justification/Explanation: Enter a brief justification or explanation for the requested action. Use this box to add any additional information such as additional account strings, or other information essential for contract execution.

Legal Contract Number: Provide the existing City contract number if applicable. This will be the same number as your POA number.

Contract Date: Select the effective date for the contract using the calendar option in the form. Leave blank for contracts to become effective on the execution date.

Change Order/AMD #: Provide the applicable Change Order or Amendment number represented by this request.

Date: Enter the date of PAF submission.

Effective Date: Enter the effective date of requested authority and/or action.

Solicitation: Select the competitive procurement method used (1Cloud generated prefix), enter the 1Cloud generated numbering sequence, and 1Cloud generated fiscal year of solicitation

Basis of Award: Select from Lowest Price Technical Acceptable (LPTA), Highest Price Technical Acceptable (HPTA),

Procurement Contract #: This is your PO number. Select Type, Enter Number

PO/Release Number: Enter PO Release Number

Awarded Supplier: Enter Awarded Supplier Name

Federally Funded: Select yes or no from dropdown if Federal Funds will be used.

Responses Received: This is the number of responses received.

No Bids Received: The number of responses received that indicated supplier would not bid.

Executed By: Select whether executed by OGC or JPAC / Chief of Procurement

PoP Base: Select the Period of Performance for the initial period.

Options: Period for each renewal period i.e. one (1) two (2) year.

Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

Extensions: How many extensions have we preformed after the initial base period and option periods have been completed?

JSEB Goal: Select the percentage established by JSEB.

JESB Other: Select Encouragement or Set Aside Option

Bonds Waived Pursuant to: Select authority allowing bonds to be waived.

Funding Source: Fund/Center/Account/Project/Activity, all fields are required even if zeros.

New NTE/GMP: Enter the new total not to exceed the amount. Note, this should match the contract maximum indebtedness, if applicable**.**

Contingent Amount: If your agency requests an allowance for unforeseen additional expenses, then specify the amount of your requested increase and new NTE that represents the contingency allowance. This is over and above any quote.

DMP/ODPO Amount: Enter the total Direct Materials Purchase/Owner Direct Purchase Order amount for project.

Attachments: Name any attachments included as supplemental information to the PAF.

Using Agency/BU: This should be the requesting agency/requirement owner.

Concurrence: Electronic Signature

Title: Enter the title of person electronically signing form.

**Any fields where there is no data available, or no entry is required, either leave it blank or enter N/A. Any fields where there is known data, include for informational purposes. Any changes to an original award should contain the data that is being changed and any other relevant data required for JPAC review and approval.*

Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

BID TABULATION

Title:	Emergency Hurricane Season Storm Sewer Cave-In Repair			**Hager Construction Company**		**Jax Utilities Management, Inc.**	
Bid No.:	CS-0078-24						
Close Date:	July 24, 2024						
Analyst:	David Klages						
No. Invited:	(6) No. Received: (2) Other: (2)						
Announcer:	Melissa Pierce						
Recorded By:	Michelle Spitler						
Item #	**Description**	**Unit of Measure**	**Est. Qty.**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**
1	Mobilization 6"-12"	EA	10	$ 2,750.00	$27,500.00	$ 2,612.84	$26,128.40
2	Mobilization 15"-18"	EA	10	$ 3,175.00	$31,750.00	$ 2,894.00	$28,940.00
3	Mobilization 21"-30"	EA	10	$ 3,485.00	$34,850.00	$ 3,112.54	$31,125.40
4	Mobilization 36"-48"	EA	10	$ 3,900.00	$39,000.00	$ 3,364.00	$33,640.00
5	Mobilization 54"-72"	EA	3	$ 4,400.00	$13,200.00	$ 3,781.84	$11,345.52
6	Mobilization Box Culvert	EA	1	$ 5,250.00	$ 5,250.00	$ 3,212.00	$ 3,212.00
7	Mobilization Structure	EA	5	$ 3,200.00	$16,000.00	$ 2,863.00	$14,315.00
8	Site Preparation 0' to 5' Depth	SF	500	$ 26.00	$13,000.00	$ 22.29	$11,145.00
9	Site Preparation > 5' to 10' Depth	SF	500	$ 42.00	$21,000.00	$ 17.44	$ 8,720.00
10	Site Preparation >10' to 15' Depth	SF	500	$ 48.00	$24,000.00	$ 13.05	$ 6,525.00
11	Site Preparation >15' to 18' Depth	SF	500	$ 51.00	$25,500.00	$ 12.10	$ 6,050.00
12	Collar Type 1 Repair 6"- 12"	EA	2	$ 1,455.00	$ 2,910.00	$ 1,114.00	$ 2,228.00
13	Collar Type 1 Repair 15"- 18"	EA	10	$ 1,865.00	$18,650.00	$ 1,291.00	$12,910.00
14	Collar Type 1 Repair 21"- 30"	EA	10	$ 2,345.00	$23,450.00	$ 1,412.00	$14,120.00
15	Collar Type 1 Repair 36"- 42"	EA	8	$ 2,850.00	$22,800.00	$ 1,626.00	$13,008.00
16	Collar Type 1 Repair 48"- 54"	EA	5	$ 3,375.00	$16,875.00	$ 1,727.00	$ 8,635.00
17	Collar Type 1 Repair 60"- 72"	EA	5	$ 3,865.00	$19,325.00	$ 1,084.00	$ 5,420.00
18	Collar Type 2 or 3 Repair 6"- 12"	EA	2	$ 1,675.00	$ 3,350.00	$ 1,224.00	$ 2,448.00
19	Collar Type 2 or 3 Repair 15"- 18"	EA	2	$ 1,895.00	$ 3,790.00	$ 1,390.00	$ 2,780.00
20	Collar Type 2 or 3 Repair 21"- 30"	EA	2	$ 2,255.00	$ 4,510.00	$ 1,464.00	$ 2,928.00
21	Collar Type 2 or 3 Repair 36"- 42"	EA	2	$ 2,745.00	$ 5,490.00	$ 2,028.00	$ 4,056.00
22	Collar Type 2 or 3 Repair 48"- 54"	EA	2	$ 3,165.00	$ 6,330.00	$ 2,154.00	$ 4,308.00
23	Collar Type 2 or 3 Repair 60"- 72"	EA	2	$ 3,585.00	$ 7,170.00	$ 1,012.00	$ 2,024.00
24	Collar Type 4 Repair 6"- 12"	EA	5	$ 1,685.00	$ 8,425.00	$ 1,223.00	$ 6,115.00
25	Collar Type 4 Repair 15- 18""	EA	10	$ 2,190.00	$21,900.00	$ 1,292.00	$12,920.00
26	Collar Type 4 Repair 21"- 30"	EA	8	$ 2,745.00	$21,960.00	$ 1,392.00	$11,136.00
27	Collar Type 4 Repair 36"- 42"	EA	5	$ 3,125.00	$15,625.00	$ 1,454.00	$ 7,270.00
28	Collar Type 4 Repair 48"- 54"	EA	5	$ 3,765.00	$18,825.00	$ 1,684.00	$ 8,420.00
29	Collar Type 4 Repair 60"- 72"	EA	1	$ 4,125.00	$ 4,125.00	$ 1,725.00	$ 1,725.00
30	Area Rigid Pipe, Box Culvert or Struct. Repair	SF	10	$ 325.00	$ 3,250.00	$ 65.00	$ 650.00
31	Area Flexible Pipe Repair	SF	10	$ 750.00	$ 7,500.00	$ 65.00	$ 650.00
32	Remove & Replace Rigid Pipe 6"	LF	20	$ 190.00	$ 3,800.00	$ 35.00	$ 700.00
33	Remove & Replace Rigid Pipe 8"	LF	20	$ 275.00	$ 5,500.00	$ 49.00	$ 980.00

Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

BID TABULATION

Title:	Emergency Hurricane Season Storm Sewer Cave-In Repair			**Hager Construction Company**		**Jax Utilities Management, Inc.**	
Bid No.:	CS-0078-24						
Close Date:	July 24, 2024						
Analyst:	David Klages						
No. Invited:	(6) No. Received: (2) Other: (2)						
Announcer:	Melissa Pierce						
Recorded By:	Michelle Spitler						
Item #	**Description**	**Unit of Measure**	**Est. Qty.**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**
34	Remove & Replace Rigid Pipe 10"	LF	20	$ 315.00	$ 6,300.00	$ 54.00	$ 1,080.00
35	Remove & Replace Rigid Pipe 12"	LF	20	$ 350.00	$ 7,000.00	$ 61.00	$ 1,220.00
36	Remove & Replace Rigid Pipe 15"	LF	50	$ 385.00	$19,250.00	$ 83.00	$ 4,150.00
37	Remove & Replace Rigid Pipe 18"	LF	50	$ 400.00	$20,000.00	$ 94.00	$ 4,700.00
38	Remove & Replace Rigid Pipe 24"	LF	24	$ 425.00	$10,200.00	$ 120.00	$ 2,880.00
39	Remove & Replace Rigid Pipe 30"	LF	16	$ 480.00	$ 7,680.00	$ 184.00	$ 2,944.00
40	Remove & Replace Rigid Pipe 36"	LF	8	$ 500.00	$ 4,000.00	$ 216.00	$ 1,728.00
41	Remove & Replace Rigid Pipe 42"	LF	8	$ 525.00	$ 4,200.00	$ 264.00	$ 2,112.00
42	Remove & Replace Rigid Pipe 48"	LF	8	$ 575.00	$ 4,600.00	$ 298.00	$ 2,384.00
43	Remove & Replace Rigid Pipe 54"	LF	8	$ 615.00	$ 4,920.00	$ 436.00	$ 3,488.00
44	Remove & Replace Rigid Pipe 60"	LF	8	$ 675.00	$ 5,400.00	$ 474.00	$ 3,792.00
45	Remove & Replace Rigid Pipe 66"	LF	8	$ 700.00	$ 5,600.00	$ 478.00	$ 3,824.00
46	Remove & Replace Rigid Pipe 72"	LF	8	$ 725.00	$ 5,800.00	$ 498.00	$ 3,984.00
47	Remove & Replace Flexible Pipe 6"	LF	100	$ 210.00	$21,000.00	$ 35.00	$ 3,500.00
48	Remove & Replace Flexible Pipe 8"	LF	20	$ 310.00	$ 6,200.00	$ 49.00	$ 980.00
49	Remove & Replace Flexible Pipe 10"	LF	20	$ 425.00	$ 8,500.00	$ 54.00	$ 1,080.00
50	Remove & Replace Flexible Pipe 12"	LF	20	$ 515.00	$10,300.00	$ 61.00	$ 1,220.00
51	Remove & Replace Flexible Pipe 15"	LF	20	$ 550.00	$11,000.00	$ 83.00	$ 1,660.00
52	Remove & Replace Flexible Pipe 18"	LF	20	$ 615.00	$12,300.00	$ 94.00	$ 1,880.00
53	Remove & Replace Flexible Pipe 24"	LF	20	$ 650.00	$13,000.00	$ 120.00	$ 2,400.00
54	Remove & Replace Flexible Pipe 30"	LF	20	$ 675.00	$13,500.00	$ 184.00	$ 3,680.00
55	Remove & Replace Flexible Pipe 36"	LF	20	$ 700.00	$14,000.00	$ 216.00	$ 4,320.00
56	Remove & Replace Flexible Pipe 42"	LF	20	$ 715.00	$14,300.00	$ 264.00	$ 5,280.00
57	Remove & Replace Flexible Pipe 48"	LF	20	$ 775.00	$15,500.00	$ 298.00	$ 5,960.00
58	Remove & Replace Flexible Pipe 54"	LF	10	$ 815.00	$ 8,150.00	$ 436.00	$ 4,360.00
59	Remove & Replace Flexible Pipe 60"	LF	10	$ 850.00	$ 8,500.00	$ 474.00	$ 4,740.00
60	Remove & Replace Flexible Pipe 66"	LF	10	$ 885.00	$ 8,850.00	$ 478.00	$ 4,780.00
61	Remove & Replace Flexible Pipe 72"	LF	10	$ 925.00	$ 9,250.00	$ 498.00	$ 4,980.00
62	Cementitious Water-Stop/Waterproofing	SF	100	$ 125.00	$12,500.00	$ 17.23	$ 1,723.00
63	Mobilization 6"-12"	EA	2	$ 3,395.00	$ 6,790.00	$ 1,662.00	$ 3,324.00
64	Mobilization 15"-18"	EA	10	$ 3,500.00	$35,000.00	$ 2,644.00	$26,440.00
65	Mobilization 21"-30"	EA	10	$ 3,750.00	$37,500.00	$ 2,863.00	$28,630.00
66	Mobilization 36"-48"	EA	35	$ 3,895.00	#########	$ 3,250.00	#########

Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

BID TABULATION

Title:	Emergency Hurricane Season Storm Sewer Cave-In Repair			**Hager Construction Company**		**Jax Utilities Management, Inc.**	
Bid No.:	CS-0078-24						
Close Date:	July 24, 2024						
Analyst:	David Klages						
No. Invited:	(6) No. Received: (2) Other: (2)						
Announcer:	Melissa Pierce						
Recorded By:	Michelle Spitler						
Item #	**Description**	**Unit of Measure**	**Est. Qty.**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**
67	Mobilization 54"-72"	EA	25	$ 4,175.00	#########	$ 3,429.00	$85,725.00
68	Mobilization Box Culvert	EA	5	$ 4,275.00	$21,375.00	$ 3,041.00	$15,205.00
69	Mobilization Structure	EA	15	$ 4,150.00	$62,250.00	$ 2,796.00	$41,940.00
70	Site Preparation 0' to 5' Depth	SF	500	$ 26.00	$13,000.00	$ 24.65	$12,325.00
71	Site Preparation > 5' to 10' Depth	SF	500	$ 26.00	$13,000.00	$ 18.68	$ 9,340.00
72	Site Preparation >10' to 15' Depth	SF	500	$ 50.00	$25,000.00	$ 13.94	$ 6,970.00
73	Site Preparation >15' to 18' Depth	SF	500	$ 50.00	$25,000.00	$ 11.05	$ 5,525.00
74	Collar Type 5 Repair 6"-12"	EA	2	$ 2,495.00	$ 4,990.00	$ 717.00	$ 1,434.00
75	Collar Type 5 Repair 15"-18"	EA	5	$ 2,785.00	$13,925.00	$ 1,184.00	$ 5,920.00
76	Collar Type 5 Repair 21"-30"	EA	5	$ 3,480.00	$17,400.00	$ 2,252.00	$11,260.00
77	Collar Type 5 Repair 36"-42"	EA	5	$ 3,695.00	$18,475.00	$ 2,486.00	$12,430.00
78	Collar Type 5 Repair 48"-54"	EA	5	$ 4,150.00	$20,750.00	$ 2,762.00	$13,810.00
79	Collar Type 5 Repair 60"-72"	EA	5	$ 4,250.00	$21,250.00	$ 3,332.00	$16,660.00
80	Unspecified LF Repair	LF	200	$ 315.00	$63,000.00	$ 101.00	$20,200.00
81	Unspecified Gallon Repair	GAL	200	$ 295.00	$59,000.00	$ 172.00	$34,400.00
82	Maintenance of Traffic (Two Lane, 2-way traffic)	EA	5	$ 3,690.00	$18,450.00	$ 480.00	$ 2,400.00
83	Maintenance of Traffic (Multi Lane, 1-way traffic)	EA	5	$ 3,856.00	$19,280.00	$ 650.00	$ 3,250.00
84	Maintenance of Traffic (Multi Lane, 2-way traffic)	EA	5	$ 4,125.00	$20,625.00	$ 725.00	$ 3,625.00
85	Maintenance of Traffic (Closure)	EA	5	$ 3,395.00	$16,975.00	$ 1,200.00	$ 6,000.00
86	Parking Meter Closure	EA	10	$ 32.00	$ 320.00	$ 32.00	$ 320.00
87	Message Board	DAY	15	$ 175.00	$ 2,625.00	$ 44.00	$ 660.00
88	Mobilization (Roadway and Right of Way)	EA	2	$ 4,195.00	$ 8,390.00	$ 1,941.00	$ 3,882.00
89	Mobilization (Asphaltic Concrete Milling >50 sq. yds.)	EA	2	$ 4,380.00	$ 8,760.00	$ 1,420.00	$ 2,840.00
90	Mobilization (Asphaltic Concrete Paving)	EA	2	$ 5,875.00	$11,750.00	$ 1,420.00	$ 2,840.00
91	Case X Asphaltic Concrete Paving Repair	SY	1,000	$ 210.00	#########	$ 50.48	$50,480.00
92	Asphaltic Concrete	Ton	50	$ 568.00	$28,400.00	$ 480.00	$24,000.00
93	Concrete Removal, Haul and Disposal	SY	50	$ 48.00	$ 2,400.00	$ 16.30	$ 815.00
94	Asphaltic Milling (1.5" Depth)	SY	50	$ 91.00	$ 4,550.00	$ 7.00	$ 350.00
95	Limerock (6" Lift)	SY	50	$ 48.00	$ 2,400.00	$ 16.00	$ 800.00
96	Limerock (Additional 1" Lift)	SY	50	$ 17.00	$ 850.00	$ 3.00	$ 150.00
97	Crushed Concrete (6" Lift)	SY	50	$ 54.00	$ 2,700.00	$ 16.00	$ 800.00
98	Crushed Concrete (Additional 1" Lift)	SY	50	$ 12.00	$ 600.00	$ 3.00	$ 150.00
99	Stabilized Subgrade (Vehicular Traffic Bearing Areas)	SY	50	$ 26.00	$ 1,300.00	$ 12.00	$ 600.00

Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

BID TABULATION

Title:	Emergency Hurricane Season Storm Sewer Cave-In Repair			**Hager Construction Company**		**Jax Utilities Management, Inc.**	
Bid No.:	CS-0078-24						
Close Date:	July 24, 2024						
Analyst:	David Klages						
No. Invited:	(6) No. Received: (2) Other: (2)						
Announcer:	Melissa Pierce						
Recorded By:	Michelle Spitler						
Item #	**Description**	**Unit of Measure**	**Est. Qty.**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**
100	Curb & Gutter (City standard, median, drop, header & Miami)	LF	500	$ 42.00	$21,000.00	$ 41.00	$20,500.00
101	Concrete Sidewalk (4" depth)	SY	200	$ 84.00	$16,800.00	$ 53.00	$10,600.00
102	Concrete Sidewalk (5" depth)	SY	200	$ 87.00	$17,400.00	$ 55.00	$11,000.00
103	Concrete Handicapped Ramp (5" depth)	SY	30	$ 125.00	$ 3,750.00	$ 71.00	$ 2,130.00
104	Concrete Driveway (5" depth)	SY	100	$ 87.00	$ 8,700.00	$ 58.00	$ 5,800.00
105	Concrete Driveway (6" depth)	SY	50	$ 94.00	$ 4,700.00	$ 67.00	$ 3,350.00
106	Cementitious Non-Shrink Grout/Plaster	SF	50	$ 134.00	$ 6,700.00	$ 14.00	$ 700.00
107	Structure Modification Brick	CF	40	$ 167.00	$ 6,680.00	$ 16.00	$ 640.00
108	Structure Modification Sawcut (= or < 8" Depth)	LF	20	$ 26.00	$ 520.00	$ 18.00	$ 360.00
109	Structure Modification Concrete and Steel	CY	5	$ 2,675.00	$13,375.00	$ 2,750.00	$13,750.00
110	Miscellaneous Concrete (Non-reinforced)	CY	1	$ 1,700.00	$ 1,700.00	$ 690.00	$ 690.00
111	Miscellaneous Concrete (Reinforced)	CY	5	$ 2,115.00	$10,575.00	$ 1,130.00	$ 5,650.00
112	New Structure (Inlet, Manhole or Endwall)	CF	50	$ 315.00	$15,750.00	$ 15.68	$ 784.00
113	Manhole Cover and Frame	EA	1	$ 3,100.00	$ 3,100.00	$ 1,480.00	$ 1,480.00
114	Catch Basin or Curb Inlet Grate and Frame	EA	1	$ 3,200.00	$ 3,200.00	$ 1,692.00	$ 1,692.00
115	Curb Iron	EA	1	$ 1,850.00	$ 1,850.00	$ 910.00	$ 910.00
116	Type "E" Grates and Frames (Traffic bearing)	EA	1	$ 1,385.00	$ 1,385.00	$ 2,210.00	$ 2,210.00
117	1" Steel Plate (Including openings, anchors and welds)	SF	100	$ 54.00	$ 5,400.00	$ 8.90	$ 890.00
118	Sand- Cement Rip-Rap Endwall	Bag	350	$ 80.00	$28,000.00	$ 16.00	$ 5,600.00
119	Rip Rap Over Filter Fabric	SY	100	$ 155.00	$15,500.00	$ 82.00	$ 8,200.00
120	A-3 Fill	CY	1,000	$ 26.00	$26,000.00	$ 29.00	$29,000.00
121	Stone (No. 57 or Equivalent)	CY	1,000	$ 84.00	$84,000.00	$ 68.00	$68,000.00
122	Over Excavation	CY	100	$ 26.00	$ 2,600.00	$ 8.00	$ 800.00
123	Pipe Encasement	CY	200	$ 380.00	$76,000.00	$ 10.23	$ 2,046.00
124	Connect (< 15" pipe to existing structure)	EA	5	$ 2,575.00	$12,875.00	$ 398.00	$ 1,990.00
125	Connect (15" to 24" pipe to existing structure)	EA	5	$ 2,985.00	$14,925.00	$ 435.00	$ 2,175.00
126	Connect (30" to 42" pipe to existing structure)	EA	1	$ 3,895.00	$ 3,895.00	$ 486.00	$ 486.00
127	Connect (48" to 60" pipe to existing structure)	EA	1	$ 4,470.00	$ 4,470.00	$ 665.00	$ 665.00
128	Connect (66" to 72" pipe to existing structure)	EA	1	$ 4,875.00	$ 4,875.00	$ 1,229.00	$ 1,229.00
129	Connect (New structure to existing <15" pipe)	EA	1	$ 2,685.00	$ 2,685.00	$ 638.00	$ 638.00
130	Connect (New structure to existing 15" to 24" pipe)	EA	1	$ 2,788.00	$ 2,788.00	$ 737.00	$ 737.00
131	Connect (New structure to existing 30" to 42" pipe)	EA	1	$ 3,395.00	$ 3,395.00	$ 870.00	$ 870.00
132	Connect (New structure to existing 48" to 60" pipe)	EA	1	$ 3,785.00	$ 3,785.00	$ 1,190.00	$ 1,190.00

Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

BID TABULATION

Title:	Emergency Hurricane Season Storm Sewer Cave-In Repair			**Hager Construction Company**		**Jax Utilities Management, Inc.**	
Bid No.:	CS-0078-24						
Close Date:	July 24, 2024						
Analyst:	David Klages						
No. Invited:	(6) No. Received: (2) Other: (2)						
Announcer:	Melissa Pierce						
Recorded By:	Michelle Spitler						
Item #	**Description**	**Unit of Measure**	**Est. Qty.**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**
133	Connect (New structure to existing 66" to 72" pipe)	EA	1	$ 4,490.00	$ 4,490.00	$ 1,370.00	$ 1,370.00
134	Seed and Mulch	SY	1,000	$ 17.00	$17,000.00	$ 3.25	$ 3,250.00
135	Grassing Sod	SY	1,000	$ 26.00	$26,000.00	$ 7.24	$ 7,240.00
136	Tree Removal (6" to 12" diameter)	EA	5	$ 1,100.00	$ 5,500.00	$ 1,360.00	$ 6,800.00
137	Tree Removal (13" to 24" diameter)	EA	4	$ 1,485.00	$ 5,940.00	$ 2,241.00	$ 8,964.00
138	Tree Removal (25" to 36" diameter)	EA	3	$ 3,375.00	$10,125.00	$ 3,950.00	$11,850.00
139	Tree Removal (> 36" diameter) adjust per 4" additional diameter	EA	2	$ 3,755.00	$ 7,510.00	$ 1,670.00	$ 3,340.00
140	Chain Link Fence (New construction, City Standard, 4' height)	LF	25	$ 26.00	$ 650.00	$ 25.00	$ 625.00
141	Chain Link Fence (New construction, City Standard, 5' height)	LF	25	$ 31.00	$ 775.00	$ 28.00	$ 700.00
142	Chain Link Fence (New Construction, City Standard, 6' height)	LF	25	$ 40.00	$ 1,000.00	$ 39.00	$ 975.00
143	Wood Privacy Fence (New Construction, All Styles, 6' height)	LF	25	$ 50.00	$ 1,250.00	$ 58.00	$ 1,450.00
144	Vinyl Privacy Fence (New Construction, All Styles, 6' height)	LF	25	$ 50.00	$ 1,250.00	$ 69.00	$ 1,725.00
145	Pavement Marking (Painted Stripes and Stop Bars, All Colors)	SF	100	$ 12.00	$ 1,200.00	$ 4.90	$ 490.00
146	Pavement Marking (Thermoplastic Stripes and Stop Bars, All Colors)	SF	100	$ 12.00	$ 1,200.00	$ 4.00	$ 400.00
147	Pavement Marking (Painted Arrows, Symbols, Etc., All Colors)	SF	50	$ 12.00	$ 600.00	$ 4.90	$ 245.00
148	Pavement Marking (Thermoplastic Arrows, Symbols, Etc., All Colors)	SF	50	$ 12.00	$ 600.00	$ 5.00	$ 250.00
149	Pavement Marking (Retro-Reflective Pavement Markers)	EA	10	$ 31.00	$ 310.00	$ 31.00	$ 310.00
150	Inductive Loop Assembly (TYPE F- 6' X 30') (660- 2-106)	EA	1	$ 3,280.00	$ 3,280.00	$ 3,080.00	$ 3,080.00
151	Underdrain	LF	25	$ 425.00	$10,625.00	$ 64.00	$ 1,600.00
152	Underdrain Cleanout	EA	1	$ 875.00	$ 875.00	$ 188.00	$ 188.00
153	Underdrain Connection	EA	5	$ 1,100.00	$ 5,500.00	$ 315.00	$ 1,575.00
154	Flowable Fill	CY	50	$ 265.00	$13,250.00	$ 410.00	$20,500.00
155	Steel Sheeting and Plates (Install and Remove)	SF	100	$ 135.00	$13,500.00	$ 27.00	$ 2,700.00
156	ByPass Pumping (> 4" Diameter)	DAY	5	$ 1,200.00	$ 6,000.00	$ 315.00	$ 1,575.00
157	Mechanical Cleaning	CY	1,000	$ 63.00	$63,000.00	$ 10.00	$10,000.00
158	Miscellaneous Cave-In Labor (4 man crew plus Foreman)	HR	20	$ 725.00	$14,500.00	$ 429.00	$ 8,580.00
159	Miscellaneous Cave-In Materials ($100 material cost plus 20%)	EA	10	$ 120.00	$ 1,200.00	$ 120.00	$ 1,200.00
160	Miscellaneous Cave-In Equipment ($100 rental cost includes operator)	EA	10	$ 100.00	$ 1,000.00	$ 100.00	$ 1,000.00
161	Storm Sewer System Investigation	HR	8	$ 300.00	$ 2,400.00	$ 359.00	$ 2,872.00
162	Project Sign	EA	1	$ 875.00	$ 875.00	$ 425.00	$ 425.00
163	Project Site Records	EA	25	$ 261.00	$ 6,525.00	$ 263.00	$ 6,575.00
			Total Bid (Line Items 1 - 163):	**$2,503,498.00**		**$1,285,272.32**	

Docusign Envelope ID: 3D4D2C44-937F-459F-9B5E-833C19A94A4D

BID TABULATION
SUMMARY

		Hager Construction Company	Jax Utilities Management, Inc.
Title:	Emergency Hurricane Season Storm Sewer Cave-In Repair		
Bid No.:	CS-0078-24		
Close Date:	July 24, 2024		
Analyst:	David Klages		
No. Invited:	(6) **No. Received:** (2) **Other:** (2)		
Announcer:	Melissa Pierce		
Recorded By:	Michelle Spitler		
Total Bid (Items 1 - 163):		**$2,503,498.00**	**$1,285,272.32**
Signed Bid Form:		Yes	Yes
Bid Proposal Form:		Yes	Yes
Conflict of Interest Certificate:		Yes	Yes
Acknowledgement/Commitment Form - Ex-Offenders:		No	Yes
JSEB Forms:		Yes	Yes
Section 21 Forms:		Yes	Yes
Bid Bond:		Yes	Yes
Addenda 1 & 2:		Yes	Yes

B. BASIS OF AWARD

The project may be awarded to the lowest responsive, responsible Bidder for the Total Bid contingent on the availability of funds within the project's approved budget. The City has the right to reject any or all bids if it is in the best interest of the City.

C. REVISIONS OF BID PROPOSAL FORM

Request for revision of the Bid Proposal Form must be made to the ENGINEER at least ten (10) days prior to date of opening of Bids. Revision of the Bid Proposal by the Bidder will void the Bid.

D. CONTRACT EXPIRATION DATE

The Contract expiration date shall be established 120 calendar days after the scheduled construction completion date in order to comply with Executive Order 2013-05.

E. BID CHANGES

No changes in the amount of Bids appearing on the outside of Bids will be considered. Only the amounts shown on bidding documents inside the envelope will be considered. All changes, corrections and erasures must be initialed by the person signing the bid.

F. CONSTRUCTION COMPLETION

The intent of this contract is that the Contractor provides **EMERGENCY HURRICANE SEASON STORM SEWER CAVE-IN REPAIR** for an initial period of three (3) years from the date of the executed contract. The Contractor shall begin work within ten (10) calendar days, including Sundays and holidays, after issuance of a Blanket Order or Purchase Order from the City, assuming conditions are safe. No Blanket Orders or Purchase Orders will be issued under this Contract after September 30, 2027 unless the Contract is renewed. The active Contract will expire 120 days thereafter. All work started under a Blanket Order or Purchase Order shall be completed by the expiration date. By mutual agreement of both parties, provided funds are available, the Contract may be extended one (1) time for a period of two (2) years. The extension amendment of the contract will be amended prior to September 30, 2027.

Based upon the agreement of all parties, the Contract Unit Prices may be adjusted one (1) time per year, after the initial year, based on the stated Consumer Price Index (CPI) for All Urban Consumers – South Region All Items, (Series CUURO300SAO), over the preceding twelve (12) months from the latter of the date of executed contract or the date of the previously approved Contract Unit Price rate adjustments. The adjusted Contract Unit Prices will be calculated using the current Contract Unit Prices and adjusting them by the amount of the stated CPI.

EMERGENCY HURRICANE SEASON STORM SEWER CAVE-IN REPAIR

SECTION 30

SCOPE OF WORK

30.1 Scope:
Emergency Hurricane Season Storm Sewer Cave-In Repair consists of the Contractor furnishing all labor, materials, and equipment for the emergency repair of failed storm sewer systems due to hurricanes or other natural catastrophic weather events, including roadway work, incidental sidewalk, driveway, curb and gutter, and/or other supporting appurtenant work, as deemed necessary at various designated locations within the limits of the City of Jacksonville.

30.2 Intent:
It is the intent of these Contract Documents to provide a continuing contract between the City of Jacksonville and a qualified Contractor during for emergency repair of failed storm sewer systems and appurtenant work as necessary due to hurricanes or other natural catastrophic weather events.

It is not the intent of these Contract Documents to minutely define the mode, means, methods, techniques, sequence of construction, and/or programs incident to the Contractor's work, but rather to set forth rational and reasonable criteria for the construction thereof.

30.3 Construction Plans:
The City of Jacksonville may supply construction drawings, as-builts, GIS infrastructure maps, or sketches for selected project sites. The Contractor shall construct the project in accordance with the Specifications and plans provided. Other project sites will be constructed as approved by the Chief of the Right of Way and Stormwater Maintenance Division.

A City of Jacksonville Representative and the Contractor shall meet on each project site to discuss the specific site's scope of work prior to the Contractor mobilizing. The conclusion will result in an agreed type of repair necessary to complete the work. At no time shall the Contractor dictate unit prices or quantities required to produce a complete project.

The Contractor shall obtain all required permits (local, State, and Federal), including, but not limited to, the NPDES Permit and the approval of the Maintenance of Traffic Plan prior to commencement of the work. The Contractor must adhere to all permit requirements.

30.4 Location:
Work sites for this project will be located within the limits of the City of Jacksonville/Duval County. Work may take place on any street, highway, on City property, or on private property with an approved easement. The South Area includes all of the City south and east of the St. Johns River and extending south to the to the St. Johns County Line.