SUBJECT: URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR

BID #: CF-0043-20 **OPEN DATE:** 2019-01-15

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT: CONSTRUCTION FIXED

AGENCY: PUBLIC WORKS

BASIS OF AWARD: SUM TOTAL BASE BID (PART A, PART B AND C -LOWEST RESPOSIVE, RESPONSIBLE BIDDER

NUMBER OF BIDS INVITED: (6) **NUMBER RECEIVED:** (3) **OTHER** (0)

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:
Recommend approval of award to the lowest responsive, responsible bidder J.B. Coxwell Contracting, Inc., in the amount of $25,456,249.15 (Part A) (city's portion); Part B in the amount of $121,427.37, Part C - $268,824.02 ($390,251.39 total) will be awarded by JEA in a separate agreement. Total award amount not-to-exceed $25,846,500.54.

This award is to be funded by account(s): PWCP331SD541-06505-PW0262-02-PWS077-19- $12,462,500.00; PWCP331SD541-06505-PW0262-02-PWS076-19- $6,496,874.58; PWCP32ERD549-06505-PW0262-02- $6,492.00; PWCP32ERD549-069505-PW0262-02- $6,490,382.57, and JEA $390,251.39 to be executed by formal contract through Office of General Counsel.

Attachments: Recommendation Memo, Bid Tabulation Sheet, Basis of Award, Scope of Work

ANALYST: _____ **RESPECTFULLY SUBMITTED** _____
MARILYN LAIDLER
GREGORY PEASE, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: Robin G. Smith, Chief, Engineering & Construction Management Division

---

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

ACTION OF AWARDING AUTHORITY DATE _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

City of Jacksonville, Florida

Lenny Curry, Mayor

Department of Public Works
214 N. Hogan St., 10th floor
Jacksonville, FL 32202
(904) 255-8786
www.coj.net

ONE CITY. ONE JACKSONVILLE.

January 17, 2020

TO: Gregory W. Pease
Chief of Procurement

THRU: John P. Pappas, P.E.
Director

FROM: Robin G. Smith, P.E.
Chief, Engineering and Construction Management

SUBJECT: RECOMMENDATION TO AWARD

RE: Urban Core Riverfront Revitalization & Complete Streets: Hart Bridge Expressway & Talleyrand Connector

Bid No.:	CF-0043-20
Bid Date:	January 15, 2020
Award Amount:	$25,456,249.15
Internal Services Account No.	PWEN011AD

The Department of Public Works reviewed and tabulated the Three (3) bids received on the referenced project. While our tabulation of the bids turned up minor corrections in the bids, no errors were significant enough to change the lowest bidder. The apparent low bid is by J. B. Coxwell Contracting, Inc. Part A will be funded by the City in the amount of $25,456,249.15 and Parts B & C will be funded by JEA in a separate agreement in the amount of $390,251.39. Public Works has confirmed through www.myfloridalicense.com the appropriate licenses for this contractor and listed subcontractors, if applicable. In addition, since a portion of the funds are to be provided by Florida Department of Transportation (FDOT), they have also reviewed and approved the bid and award.

Accordingly, we recommend that the Total Base Bid for Urban Core Riverfront Revitalization & Complete Streets: Hart Bridge Expressway & Talleyrand Connector be awarded to J B. Coxwell Contracting, Inc. 6741 Lloyd Road West, Jacksonville, FL 32254, in accordance with the attached bid documents, for Part A in the amount of $25,456,249.15 which is being funded by the City, and Parts B & C in the amount of $390,251.39 to be awarded by JEA in a separate agreement for a total of $25,846,500.54.

Funding for this project should be encumbered by contract as follows:

ACCOUNT NO.	ENCUMBERED AMOUNT
PWCP331SD541-06505-PW0262-02-PWS077-19	$12,462,500.00
PWCP331SD541-06505-PW0262-02-PWS076-19	$6,496,874.58
PWCP32ERD549-06505-PW0262-02	$6,492.00
PWCP32ERD549-069505-PW0262-02	$6,490,382.57
JEA	$390,251.39
TOTALS	$25,846,500.54

RGS/lw

Attachments

cc: Lori West, PW Contract Specialist, Engineering and Construction Management
Gary Goldsberry, P.E., Project Manager, Engineering and Construction Management

Laidler, Marilyn

From:	Hall, Gregory (FHWA) <Gregory.Hall@dot.gov>
Sent:	Friday, January 17, 2020 2:49 PM
To:	Goldsberry, Gary; Roberson, Amy; Laidler, Marilyn; Clark Williams
Cc:	Joyce, William; Jackson, J. Keith; Pease, Gregory; Brackin, Ann; West, Lori; Driggers Jr., James (James.DriggersJr@dot.state.fl.us); Cerlanek, William (William.Cerlanek@dot.state.fl.us)
Subject:	RE: Urban Core Riverfront Revitalization and Complete Streets: Hart Bridge Expressway & Talleyrand Connector
Importance:	High

EXTERNAL EMAIL: This email originated from a non-COJ email address. Do not click any links or open any attachments unless you trust the sender and know the content is safe.

All,

After reviewing the bid tab, for the most part, the bid unit prices are acceptable. Some items exceeded 150% of the engineer's estimate and a couple exceed 250% of the engineer's estimate (EE) as discussed below:

- #35 – Mowing – 158% above EE
- #41 – Regular Excavation – 164% above EE
- #66A – Pipe Culvert Round 15" – 159 % above EE
- #92 – Guardrail TL-2 – **747%** above EE
    - Note that FHWA does not normally participate in items damaged by 3rd parties... so overruns in guardrail due to impacts by motorists (after the initial installation of the guardrail) would be non-participating.
    - Overall contract value is low.
- #128 – Concrete Class NS, Gravity wall – 251% above EE
- #132 – Concrete Class IV Bulkhead – 170% above EE
- #154 – Structural Steel, Low Alloy – 180% above EE
- #156 – Bridge Drains – 212% above EE
- #184 – Sign Panel Relocation – 248% above EE
- #254 – Vehicle Detection Equipment – 390% above EE
- #256 – Vehicle Detection Equipment – 193% above EE

Other than the guardrail and excavation, the other items identified above do not strike me as likely to experience much in the way of overruns (short of major plan revisions). Thankfully most of them don't seem to have a significant overall cost impact when compared to the total contract value. But I wanted to make sure the CoJ is mindful of these mark-ups in case future change orders are needed that might result in overruns or change orders on these items.

Almost all of the JEA lighting items are in excess of 200%, with some items being 1160%, 798%, and three between 400% and 500%. So if those items overrun, JEA needs to be prepared for that. But again, these mark ups percentages do not appear to amount to a significant amount of overall project costs.

Overall though, FHWA acknowledges that the total bid is less than the engineer's estimate (largely attributable to the difference in unit prices of the demolition of the existing bridges). Additionally, there do not appear to be any obvious mathematical or material imbalances. As such, FHWA concurs with the City of Jacksonville's recommendation to award to JB Coxwell.

I have also received confirmation from FDOT that they have no objections. The CoJ may proceed with their recommended selection for award.

Thanks for the quick responses to information requests.
-Greg

Greg Hall
D2 Transportation Engineer
FHWA - Florida Division
3500 Financial Plaza, Suite 400
Tallahassee, FL 32312

FDOT Mail Stop #29
Direct Line: (850) 553-2232
Office Line: (850) 553-2200
Gregory.Hall@dot.gov

From: Goldsberry, Gary [mailto:GGoldsberry@coj.net]
Sent: Friday, January 17, 2020 9:45 AM
To: Roberson, Amy <Amy.Roberson@dot.state.fl.us>; Hall, Gregory (FHWA) <Gregory.Hall@dot.gov>; Laidler, Marilyn <MLaidler@coj.net>; Clark Williams <clark@flablueprint.com>
Cc: Joyce, William <JOYCE@coj.net>; Jackson, J. Keith <keith.jackson@stvinc.com>; Pease, Gregory <GPease@coj.net>; Brackin, Ann <ABRACKIN@coj.net>; West, Lori <LWEST@coj.net>
Subject: Urban Core Riverfront Revitalization and Complete Streets: Hart Bridge Expressway & Talleyrand Connector

Amy and Greg,
I have attached a copy of the Recommendation to Award that is an internal document for processing the award to the desired bidder, in this case, J.B. Coxwell. This document will be finalized and processed once we receive your concurrence on the selection. As you may be aware, the City has decided to modify the most recent schedule attached schedule and move the Award Committee Meeting from January 30, 2020 up one week to January 23, 2020. To do this we will need your concurrence by COB today. Please contact me with any question you may have.

All the Best,

Gary J. Goldsberry, P.E.
Engineering Design Section
Department of Public Works
214 N. Hogan Street, 10th Floor
Jacksonville, FL 32202
(904) 255-8709
Email: ggoldsberry@coj.net

Florida Department of Transportation

RON DESANTIS
GOVERNOR

1109 South Marion Avenue
Lake City, Florida 32025-5874

KEVIN J. THIBAULT
SECRETARY

January 21, 2020

Mr. Robin Smith, P.E., Chief Engineer
City of Jacksonville
214 N. Hogan Street
Jacksonville, Florida 32202

Subject: **Concurrence in Award of Contract – Sent Via Email**
Project description: Urban Core Riverfront Revitalization and Complete Streets: Hart Bridge Expressway & Talleyrand Connector
Financial Project ID: 4433972-2-58-01
Federal Project ID: D219-120-B
Local Agency Program Agreement: G1H12

Dear Mr. Smith:

This letter serves as your notice of concurrence in the award of the subject contract to the lowest responsive bidder: **JB Coxwell Contracting, Inc.** You are authorized to proceed with award of the contract.

Once you have executed the contract, please provide us with the following information:

- Copy of the executed contract with the bid bond, required forms signed by the contractor and FHWA 1273 included

This information can be placed in the Local Agency Program Information Tool (LAPIT). All supplemental agreements and/or change orders, regardless of dollar amount/time, must be approved by the LAP Administrator prior to the effective date. Invoices and questions should be directed to Amy Roberson at amy.roberson@dot.state.fl.us or at 386-961-7363.

Sincerely,

Amy Roberson

Amy Roberson
District Local Programs Administrator

:ar

cc: William Cerlanek, P.E. District Program Management Administration Engineer
Jamie Driggers, P.E. District Program Management Engineer
Greg Hall, D2 Transportation Engineer, FHWA – Florida Division

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
OPEN DATE:	JANUARY 15, 2020 @ 2:00PM									
BUYER:	MARILYN LAIDLER									
No. Invited: (6)	No. Received (3) No Bids: (0)									
ITEM	DESCRIPTION OF WORK	PAY ITEMS	EST.QTY	UNIT	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
	PART A -ROADWAY									
1	MOBILIZATION	FDOT PAY ITEM 101 1	1	LS	$ 3,100,000.00	$ 3,100,000.00	$ 3,000,000.00	$ 3,000,000.00	2302625	$ 2,302,625.00
2	MAINTENANCE OF TRAFFIC	FDOT PAY ITEM 102 1	1	LS	$ 750,000.00	$ 750,000.00	$ 300,000.00	$ 300,000.00	$ 200,700.00	$ 200,700.00
3	TRAFFIC CONTROL OFFICER	FDOT PAY ITEM 102 14	2250	HR	$ 55.00	$ 123,750.00	$ 69.00	$ 155,250.00	$ 68.25	$ 153,562.50
4	TEMP. SIGNALIZATION AND MAINT. OF INTERSECTION	FDOT PAY ITEM 102 107 1	3300	ED	$ 25.00	$ 82,500.00	$ 7.50	$ 24,750.00	$ 15.75	$ 51,975.00
5	TEMP. TRAFFIC DETECTION	FDOT PAY ITEM 102 104	3300	ED	$ 10.00	$ 33,000.00	$ 0.75	$ 2,475.00	$ 5.25	$ 17,325.00
6	SPECIAL DETOUR 1	FDOT PAY ITEM 102 2 1	1	LS	$ 300,000.00	$ 300,000.00	$ 940,000.00	$ 940,000.00	$ 145,000.00	$ 145,000.00
7	SPECIAL DETOUR 2	FDOT PAY ITEM 102 2 2	1	LS	$ 250,000.00	$ 250,000.00	$ 135,000.00	$ 135,000.00	$ 105,500.00	$ 105,500.00
8	SPECIAL DETOUR 3	FDOT PAY ITEM 102 2 3	1	LS	$ 50,000.00	$ 50,000.00	$ 55,000.00	$ 55,000.00	$ 9,300.00	$ 9,300.00
9	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINT.	FDOT PAY ITEM 102 3	60	CY	$ 500.00	$ 30,000.00	$ 75.00	$ 4,500.00	$ 53.00	$ 3,180.00
10	PEDESTRIAN SPECIAL DETOUR 1	FDOT PAY ITEM 102 4 1	1	LS	$ 25,000.00	$ 25,000.00	$ 15,000.00	$ 15,000.00	$ 4,300.00	$ 4,300.00
11	PEDESTRIAN SPECIAL DETOUR 2	FDOT PAY ITEM 102 4 2	1	LS	$ 25,000.00	$ 25,000.00	$ 4,500.00	$ 4,500.00	$ 1,600.00	$ 1,600.00
12	PEDESTRIAN SPECIAL DETOUR 3	FDOT PAY ITEM 102 4 3	1	LS	$ 25,000.00	$ 25,000.00	$ 7,600.00	$ 7,600.00	$ 1,770.00	$ 1,770.00
13	WORK ZONE SIGN	FDOT PAY ITEM 102 60	43891	ED	$ 0.20	$ 8,778.20	$ 0.50	$ 21,945.50	$ 0.21	$ 9,217.11
14	BUSINESS SIGN	FDOT PAY ITEM 102 61	28	ED	$ 25.00	$ 700.00	$ 55.00	$ 1,540.00	$ 26.25	$ 735.00
15	BARRIER MOUNTED WORK ZONE SIGN	FDOT PAY ITEM 102 62	5072	ED	$ 0.20	$ 1,014.40	$ 1.00	$ 5,072.00	$ 0.21	$ 1,065.12
16	TEMP. LOW PROFILE BARRIER	FDOT PAY ITEM 102 71 13	3764	LF	$ 45.00	$ 169,380.00	$ 47.00	$ 176,908.00	$ 32.55	$ 122,518.20
17	TEMP. BARRIER WALL	FDOT PAY ITEM 102 71 16	665	LF	$ 30.00	$ 19,950.00	$ 27.00	$ 17,955.00	$ 16.80	$ 11,172.00

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
18	TEMP. LOW PROFILE BARRIER (RELOCATE)	FDOT PAY ITEM 102 71 23	4653	LF	$ 7.50	$ 34,897.50	$ 8.00	$ 37,224.00	$ 9.45	$ 43,970.85
19	CHANNELIZING DEVICE	FDOT PAY ITEM 102 74 1	164670	ED	$ 0.10	$ 16,467.00	$ 0.15	$ 24,700.50	$ 0.11	$ 18,113.70
20	TYPE III BARRICADE	FDOT PAY ITEM 102 74 2	26040	ED	$ 0.20	$ 5,208.00	$ 1.00	$ 26,040.00	$ 0.21	$ 5,468.40
21	PED. LCD	FDOT PAY ITEM 102 74 7	3121	LF	$ 3.00	$ 9,363.00	$ 5.00	$ 15,605.00	$ 3.15	$ 9,831.15
22	ADVANCED WARNING ARROW PANEL	FDOT PAY ITEM 102 76	870	ED	$ 5.00	$ 4,350.00	$ 8.00	$ 6,960.00	$ 5.25	$ 4,567.50
23	TEMPORARY RPM	FDOT PAY ITEM 102 78	849	EA	$ 3.00	$ 2,547.00	$ 5.00	$ 4,245.00	$ 3.68	$ 3,124.32
24	TEMP CRASH CUSHION	FDOT PAY ITEM 102 89 1	1	LO	$ 800.00	$ 800.00	$ 900.00	$ 900.00	$ 2,200.00	$ 2,200.00
25	PAV'T MARKINGS- REMOVABLE TAPE- WHITE 6"	FDOT PAY ITEM 102 911 1	522	LF	$ 2.00	$ 1,044.00	$ 3.00	$ 1,566.00	$ 2.63	$ 1,372.86
26	PAV'T MARKINGS- REMOVABLE TAPE- WHITE SKIP 6"	FDOT PAY ITEM 102 911 2	110	LF	$ 2.00	$ 220.00	$ 3.00	$ 330.00	$ 1.31	$ 144.10
27	PAV'T MARKINGS- REMOVABLE TAPE- YELLOW 6"	FDOT PAY ITEM 102 912 2	1761	LF	$ 2.00	$ 3,522.00	$ 3.00	$ 5,283.00	$ 2.63	$ 4,631.43
28	PORTABLE CHANGEABLE MESSAGE SIGN	FDOT PAY ITEM 102 99	1440	ED	$ 10.00	$ 14,400.00	$ 50.00	$ 72,000.00	$ 10.50	$ 15,120.00
29	ARTIFICAL COVERINGS	FDOT PAY ITEM 104 1	2946	SY	$ 5.00	$ 14,730.00	$ 8.00	$ 23,568.00	$ 1.71	$ 5,037.66
30	SEDIMENT BARRIER	FDOT PAY ITEM 104 10 3	8478	LF	$ 1.50	$ 12,717.00	$ 5.00	$ 42,390.00	$ 3.19	$ 27,044.82
31	FLOATING TURBIDITY BARRIER	FDOT PAY ITEM 104 11	842	LF	$ 18.00	$ 15,156.00	$ 25.00	$ 21,050.00	$ 26.30	$ 22,144.60
32	SOIL TRACKING PREVENTION DEVICE	FDOT PAY ITEM 104 15	2	EA	$ 3,700.00	$ 7,400.00	$ 6,000.00	$ 12,000.00	$ 4,111.88	$ 8,223.76
33	INLET PROTECTION SYSTEM	FDOT PAY ITEM 104 18	77	EA	$ 180.00	$ 13,860.00	$ 115.00	$ 8,855.00	$ 68.25	$ 5,255.25
34	LITTER REMOVAL	FDOT PAY ITEM 107 1	221.80	AC	$ 14.00	$ 3,105.20	$ 30.00	$ 6,654.00	$ 36.31	$ 8,053.56
35	MOWING	FDOT PAY ITEM 107 2	108.41	AC	$ 35.00	$ 3,794.35	$ 30.00	$ 3,252.30	$ 73.97	$ 8,019.09
36	MONITOR EXISTING STRUCTURES	FDOT PAY ITEM 108 1	1	LS	$ 50,000.00	$ 50,000.00	$ 13,450.00	$ 13,450.00	$ 11,000.00	$ 11,000.00
37	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING	FDOT PAY ITEM 108 2	1	LS	$ 100,000.00	$ 100,000.00	$ 39,700.00	$ 39,700.00	$ 54,000.00	$ 54,000.00
38	CLEARING AND GRUBBING	FDOT PAY ITEM 110 1 1	13.72	AC	$ 15,000.00	$ 205,800.00	$ 59,590.00	$ 817,574.80	$ 11,000.00	$ 150,920.00
39	SELECTIVE CLEARING AND GRUBBING, TREES REMAIN	FDOT PAY ITEM 110 2 2	0.129	AC	$ 14,000.00	$ 1,806.00	$ 43,000.00	$ 5,547.00	$ 318,860.00	$ 41,132.94
40	REMOVAL OF EXISTING CONCRETE	FDOT PAY ITEM 110 4 10	20177	SY	$ 22.00	$ 443,894.00	$ 0.50	$ 10,088.50	$ 7.41	$ 149,511.57

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
41	REGULAR EXCAVATION	FDOT PAY ITEM 120 1	5275	CY	$ 12.00	$ 63,300.00	$ 10.00	$ 52,750.00	$ 15.00	$ 79,125.00
42	SUBSOIL EXCAVATION	FDOT PAY ITEM 120 4	28006	CY	$ 25.00	$ 700,150.00	$ 30.00	$ 840,180.00	$ 16.00	$ 448,096.00
43	EMBANKMENT	FDOT PAY ITEM 120 6	100487	CY	$ 26.00	$ 2,612,662.00	$ 19.00	$ 1,909,253.00	$ 14.00	$ 1,406,818.00
44	FLOWABLE FILL	FDOT PAY ITEM 121 70 5	489	CY	$ 190.00	$ 92,910.00	$ 200.00	$ 97,800.00	$ 137.00	$ 66,993.00
45	TYPE B STABILIZATION	FDOT PAY ITEM 160 4	38948	SY	$ 12.00	$ 467,376.00	$ 6.50	$ 253,162.00	$ 4.12	$ 160,465.76
46	OPTIONAL BASE GROUP 4	FDOT PAY ITEM 285 704	6104	SY	$ 12.00	$ 73,248.00	$ 15.00	$ 91,560.00	$ 20.26	$ 123,667.04
47	OPTIONAL BASE GROUP 9 (TYPE B-12.5 ONLY)	FDOT PAY ITEM 285 709	16079	SY	$ 55.00	$ 884,345.00	$ 36.00	$ 578,844.00	$ 35.70	$ 574,020.30
48	OPTIONAL BASE GROUP 10	FDOT PAY ITEM 285 710	14780	SY	$ 30.00	$ 443,400.00	$ 18.00	$ 266,040.00	$ 22.97	$ 339,496.60
49	MILLING EXIST. ASPH. PAVT. 1 1/2" AVG/ DEPTH	FDOT PAY ITEM 327 70 6	16852	SY	$ 3.00	$ 50,556.00	$ 2.00	$ 33,704.00	$ 2.09	$ 35,220.68
50	SUPERPAVE ASPHALTIC CONC. TRAFFIC B	FDOT PAY ITEM 334 1 12	502.5	TN	$ 140.00	$ 70,350.00	$ 110.00	$ 55,275.00	$ 113.40	$ 56,983.50
51	SUPERPAVE ASPHALTIC CONC. TRAFFIC C (OVERBUILD)	FDOT PAY ITEM 334 1 13	1198.7	TN	$ 140.00	$ 167,818.00	$ 115.00	$ 137,850.50	$ 109.20	$ 130,898.04
52	SUPERPAVE ASPH. CONC. TRAF. C	FDOT PAY ITEM 334 1 13	3928.5	TN	$ 140.00	$ 549,990.00	$ 96.00	$ 377,136.00	$ 98.70	$ 387,742.95
53	ASPH. CONC. FC, TRAFFIC C, FC-12.5, PG76 22	FDOT PAY ITEM 337 7 83	3762.1	TN	$ 150.00	$ 564,315.00	$ 114.00	$ 428,879.40	$ 116.55	$ 438,472.76
54	MISC. ASPHALT PAVEMENT	FDOT PAY ITEM 339 1	66.8	TN	$ 200.00	$ 13,360.00	$ 250.00	$ 16,700.00	$ 153.83	$ 10,275.84
55	CONCRETE CLASS NS, GRAVITY WALL	FDOT PAY ITEM 400 011	141	CY	$ 650.00	$ 91,650.00	$ 900.00	$ 126,900.00	$ 797.00	$ 112,377.00
56	CURB INLETS, TYPE 9, P-BOT, <10'	FDOT PAY ITEM 425 1201	1	EA	$ 4,600.00	$ 4,600.00	$ 13,950.00	$ 13,950.00	$ 2,665.00	$ 2,665.00
57	CURB INLETS, TYPE 8, P-BOT, <10'	FDOT PAY ITEM 425 1481	2	EA	$ 4,600.00	$ 9,200.00	$ 9,200.00	$ 18,400.00	$ 3,010.00	$ 6,020.00
58	MEDIAN BARRIER INLETS, SINGLE, <10'	FDOT PAY ITEM 425 1781	10	EA	$ 4,600.00	$ 46,000.00	$ 4,825.00	$ 48,250.00	$ 8,320.00	$ 83,200.00
59	MEDIAN BARRIER INLETS, SINGLE, >10'	FDOT PAY ITEM 425 1782	2	EA	$ 8,500.00	$ 17,000.00	$ 13,700.00	$ 27,400.00	$ 15,485.00	$ 30,970.00
60	BARRIER WALL INLETS <10'	FDOT PAY ITEM 425 1891	4	EA	$ 4,600.00	$ 18,400.00	$ 5,950.00	$ 23,800.00	$ 4,450.00	$ 17,800.00
61	BARRIER WALL INLETS >10'	FDOT PAY ITEM 425 1892	4	EA	$ 7,500.00	$ 30,000.00	$ 12,450.00	$ 49,800.00	$ 10,000.00	$ 40,000.00
62	CURB INLETS, FLUME	FDOT PAY ITEM 425 1910	1	EA	$ 1,200.00	$ 1,200.00	$ 5,250.00	$ 5,250.00	$ 2,450.00	$ 2,450.00
63	INLET ADJUST	FDOT PAY ITEM 425 4	1	EA	$ 1,200.00	$ 1,200.00	$ 3,750.00	$ 3,750.00	$ 775.00	$ 775.00

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
64	MANHOLE ADJUST	FDOT PAY ITEM 425 5	7	EA	$ 1,200.00	$ 8,400.00	$ 1,800.00	$ 12,600.00	$ 850.00	$ 5,950.00
65	VALVE BOXES, ADJUST (VALVE & METER BOXES)	FDOT PAY ITEM 425 6	31	EA	$ 1,200.00	$ 37,200.00	$ 1,500.00	$ 46,500.00	$ 385.00	$ 11,935.00
66	MANHOLE, ADJUST, UTILITIES	FDOT PAY ITEM 425 5 1	27	EA	$ 750.00	$ 20,250.00	$ 2,800.00	$ 75,600.00	$ 835.00	$ 22,545.00
66A	PIPE CULVERT, OPTIONAL MATERIAL, ROUND 15"	FDOT PAY ITEM 430 175 115	20	LF	$ 125.00	$ 2,500.00	$ 630.00	$ 12,600.00	$ 170.00	$ 3,400.00
67	PIPE CULVERT, OPTIONAL MATERIAL, ROUND 18"	FDOT PAY ITEM 430 175 118	5335	LF	$ 65.00	$ 346,775.00	$ 119.00	$ 634,865.00	$ 71.50	$ 381,452.50
68	PIPE CULVERT, OPTIONAL MATERIAL, ROUND 24"	FDOT PAY ITEM 430 175 124	802	LF	$ 75.00	$ 60,150.00	$ 142.00	$ 113,884.00	$ 104.00	$ 83,408.00
69	PIPE CULVERT, OPTIONAL MATERIAL, ROUND 30"	FDOT PAY ITEM 430 175 130	172	LF	$ 105.00	$ 18,060.00	$ 239.00	$ 41,108.00	$ 196.00	$ 33,712.00
70	PIPE CULVERT, OPTIONAL MATERIAL, ROUND 42"	FDOT PAY ITEM 430 175 142	82	LF	$ 160.00	$ 13,120.00	$ 240.00	$ 19,680.00	$ 198.00	$ 16,236.00
71	PIPE CULVERT, OPTIONAL MATERIAL, ROUND 48"	FDOT PAY ITEM 430 175 148	225	LF	$ 225.00	$ 50,625.00	$ 226.00	$ 50,850.00	$ 233.00	$ 52,425.00
72	PIPE CULVERT, OPTIONAL MATERIAL, ELLIPTICAL 12" X 18"	FDOT PAY ITEM 430 175 215	12	LF	$ 140.00	$ 1,680.00	$ 550.00	$ 6,600.00	$ 475.00	$ 5,700.00
73	PIPE CULVERT, OPTIONAL MATERIAL, ELLIPTICAL 14" X 23"	FDOT PAY ITEM 430 175 218	38	LF	$ 150.00	$ 5,700.00	$ 129.00	$ 4,902.00	$ 132.00	$ 5,016.00
74	U-TYPE CONCRETE ENDWALL, 30"	FDOT PAY ITEM 430 611 133	1	EA	$ 4,500.00	$ 4,500.00	$ 8,200.00	$ 8,200.00	$ 2,575.00	$ 2,575.00
75	PVC PIPE FOR BACK OF SIDEWALK, 4"	FDOT PAY ITEM 430 963 01	110	LF	$ 35.00	$ 3,850.00	$ 45.00	$ 4,950.00	$ 26.00	$ 2,860.00
76	CROSSDRAIN MITERED END SECTION, 18"	FDOT PAY ITEM 430 982125	1	EA	$ 1,700.00	$ 1,700.00	$ 7,500.00	$ 7,500.00	$ 1,060.00	$ 1,060.00
77	CROSSDRAIN MITERED END SECTION, 42"	FDOT PAY ITEM 430 982133	1	EA	$ 2,600.00	$ 2,600.00	$ 10,450.00	$ 10,450.00	$ 3,385.00	$ 3,385.00
78	UNDERDRAIN, TYPE II (COJ TYPE 1)	FDOT PAY ITEM 440 1 20	3984	LF	$ 35.00	$ 139,440.00	$ 59.00	$ 235,056.00	$ 30.00	$ 119,520.00
79	STEEL PIPE HANDRAIL	FDOT PAY ITEM 515 1 1	135	LF	$ 100.00	$ 13,500.00	$ 63.00	$ 8,505.00	$ 120.44	$ 16,259.40
80	PEDESTRIAN/BICYCLE RAILING, STEEL, 42" TYPE 1	FDOT PAY ITEM 515 22 11	220	LF	$ 100.00	$ 22,000.00	$ 65.00	$ 14,300.00	$ 131.25	$ 28,875.00
81	BOLLARDS	FDOT PAY ITEM 519 78	28	EA	$ 350.00	$ 9,800.00	$ 1,900.00	$ 53,200.00	$ 1,135.00	$ 31,780.00
82	CONCRETE CURB & GUTTER, TYPE E	FDOT PAY ITEM 520 1 7	2258	LF	$ 25.00	$ 56,450.00	$ 30.00	$ 67,740.00	$ 16.22	$ 36,624.76
83	TRAFFIC SEPARATOR, CONCRETE, TYPE 1, 4' WIDE	FDOT PAY ITEM 520 5 11	213	LF	$ 40.00	$ 8,520.00	$ 78.00	$ 16,614.00	$ 48.11	$ 10,247.43
84	TRAFFIC SEPARATOR, CONC.- TYPE IV, 4' WIDE	FDOT PAY ITEM 520 5 41	238	LF	$ 40.00	$ 9,520.00	$ 88.00	$ 20,944.00	$ 46.47	$ 11,059.86

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
85	CONCRETE TRAFFIC SEPARATOR, SPECIAL VARIABLE WIDTH	FDOT PAY ITEM 520 70	230	SY	$ 50.00	$ 11,500.00	$ 105.00	$ 24,150.00	$ 41.01	$ 9,432.30
86	MEDIAN BARRIER WALL- 38" HEIGHT	FDOT PAY ITEM 521 11	832	LF	$ 113.00	$ 94,016.00	$ 75.00	$ 62,400.00	$ 193.63	$ 161,100.16
87	MEDIAN BARRIER- 44" HEIGHT VARIABLE SECTION WIDTH	FDOT PAY ITEM 521 1 14	261	LF	$ 750.00	$ 195,750.00	$ 725.00	$ 189,225.00	$ 802.20	$ 209,374.20
88	SHOULDER CONCRETE BARRIER	FDOT PAY ITEM 521 72 40	375	LF	$ 270.00	$ 101,250.00	$ 340.00	$ 127,500.00	$ 288.75	$ 108,281.25
89	SHOULDER BARRIER WALL- 38" WALL SHIELDING BARRIER	FDOT PAY ITEM 521 72 60	450	LF	$ 320.00	$ 144,000.00	$ 118.00	$ 53,100.00	$ 345.45	$ 155,452.50
90	CONCRETE SIDEWALK & DRIVEWAYS - 6" THICK	FDOT PAY ITEM 522 2	12502	LF	$ 40.00	$ 500,080.00	$ 53.00	$ 662,606.00	$ 41.32	$ 516,582.64
91	DETECTABLE WARNING	FDOT PAY ITEM 527 2	901	SF	$ 30.00	$ 27,030.00	$ 33.00	$ 29,733.00	$ 45.94	$ 41,391.94
92	GUARDRAIL TL-2	FDOT PAY ITEM 536 1 0	275	LF	$ 20.00	$ 5,500.00	$ 19.00	$ 5,225.00	$ 131.25	$ 36,093.75
93	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	FDOT PAY ITEM 536 85 20	4	EA	$ 1,300.00	$ 5,200.00	$ 1,050.00	$ 4,200.00	$ 1,100.00	$ 4,400.00
94	FENCING, TYPE B, 5.1'- 6.0', W/VINYL COATING	FDOT PAY ITEM 550 10222	759	LF	$ 53.00	$ 40,227.00	$ 35.00	$ 26,565.00	$ 32.76	$ 24,864.84
95	FENCE GATE, TYPE B, SLIDING CANTILEVER, 30' OPENING	FDOT PAY ITEM 550 60 236	1	EA	$ 7,000.00	$ 7,000.00	$ 4,000.00	$ 4,000.00	$ 4,053.00	$ 4,053.00
96	PERFORMANCE TURF, SOD	FDOT PAY ITEM 570 1 2	29457	SY	$ 3.00	$ 88,371.00	$ 6.00	$ 176,742.00	$ 3.52	$ 103,688.64
97	UTILITY CONDUIT, F&I, 9 6" DUCTS	FDOT PAY ITEM 630 2 11	1045	LF	$ 15.00	$ 15,675.00	$ 169.00	$ 176,605.00	$ 6.30	$ 6,583.50
98	CONDUIT, F&I, EMBEDDED CONC. BARRIERS	FDOT PAY ITEM 630 2 16	9117	LF	$ 15.00	$ 136,755.00	$ 6.00	$ 54,702.00	$ 14.70	$ 134,019.90
99	JUNCTION BOX, F&I, EMBEDDED	FDOT PAY ITEM 635 3 13	38	EA	$ 445.00	$ 16,910.00	$ 395.00	$ 15,010.00	$ 446.25	$ 16,957.50
100	PAV'T MARKINGS- 12" WHITE	FDOT PAY ITEM 710 111 23	2559	LF	$ 0.40	$ 1,023.60	$ 1.50	$ 3,838.50	$ 1.31	$ 3,352.29
101	PAV'T MARKINGS- 18" WHITE	FDOT PAY ITEM 710 111 24	1772	LF	$ 0.60	$ 1,063.20	$ 2.00	$ 3,544.00	$ 1.89	$ 3,349.08
102	PAV'T MARKINGS- 24" WHITE	FDOT PAY ITEM 710 111 25	4091	LF	$ 0.80	$ 3,272.80	$ 3.00	$ 12,273.00	$ 2.10	$ 8,591.10
103	PAV'T MARKINGS- 6" WHITE SKIP	FDOT PAY ITEM 710 111 31	2.04	GM	$ 345.00	$ 703.80	$ 800.00	$ 1,632.00	$ 446.25	$ 910.35
104	PAV'T MARKINGS- WHITE MESSAGE/SYMBOL	FDOT PAY ITEM 710 111 60	49	EA	$ 40.00	$ 1,960.00	$ 40.00	$ 1,960.00	$ 57.75	$ 2,829.75

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
105	PAV'T MARKINGS- WHITE ARROWS	FDOT PAY ITEM 710 111 70	151	EA	$ 30.00	$ 4,530.00	$ 30.00	$ 4,530.00	$ 36.75	$ 5,549.25
106	PAV'T MARKINGS- 6" WHITE	FDOT PAY ITEM 710 11101	11.10	GM	$ 1,030.00	$ 11,433.00	$ 1,750.00	$ 19,425.00	$ 892.50	$ 9,906.75
107	PAV'T MARKINGS- 6" YELLOW	FDOT PAY ITEM 710 112 01	7.21	GM	$ 1,030.00	$ 7,426.30	$ 1,750.00	$ 12,617.50	$ 892.50	$ 6,434.93
108	PAV'T MARKINGS- 18" YELLOW	FDOT PAY ITEM 710 112 24	1557	LF	$ 0.60	$ 934.20	$ 2.00	$ 3,114.00	$ 1.89	$ 2,942.73
109	PAV'T MARKINGS- 6" YELLOW SKIP	FDOT PAY ITEM 710 112 31	0.03	GM	$ 345.00	$ 10.35	$ 800.00	$ 24.00	$ 472.67	$ 14.18
110	SITE PREPARATION	COJ 102	1.00	LS	$ 250,000.00	$ 250,000.00	$ 1,764,762.82	$ 1,764,762.82	$ 392,500.00	$ 392,500.00
111	CONCRETE CURB & GUTTER, CITY STANDARD	COJ 131	10578	LF	$ 20.00	$ 211,560.00	$ 19.00	$ 200,982.00	$ 17.96	$ 189,980.88
112	VALLEY GUTTER- CONCRETE	COJ 131	1292	LF	$ 20.00	$ 25,840.00	$ 29.00	$ 37,468.00	$ 52.62	$ 67,985.04
113	HEADER CURB- CONCRETE	COJ 131	547	LF	$ 18.00	$ 9,846.00	$ 33.00	$ 18,051.00	$ 26.60	$ 14,550.20
114	CURB INLETS <10'	COJ 202	55	EA	$ 4,500.00	$ 247,500.00	$ 6,700.00	$ 368,500.00	$ 3,507.74	$ 192,925.70
115	CURB INLETS >10'	COJ 202	1	EA	$ 7,500.00	$ 7,500.00	$ 7,700.00	$ 7,700.00	$ 4,973.85	$ 4,973.85
116	CURB INLETS, ROUND, <10'	COJ 202	13	EA	$ 6,500.00	$ 84,500.00	$ 5,600.00	$ 72,800.00	$ 3,660.43	$ 47,585.59
117	CURB INLETS, TYPE J, <10'	COJ 202	1	EA	$ 8,500.00	$ 8,500.00	$ 7,150.00	$ 7,150.00	$ 5,491.52	$ 5,491.52
118	CURB INLETS, DOUBLE, <10'	COJ 202	3	EA	$ 7,500.00	$ 22,500.00	$ 11,550.00	$ 34,650.00	$ 6,284.77	$ 18,854.31
119	CURB INLETS, PARTIAL, <10'	COJ 202	1	EA	$ 2,500.00	$ 2,500.00	$ 4,800.00	$ 4,800.00	$ 3,985.63	$ 3,985.63
120	MANHOLES, TYPE J <10'	COJ 202	15	EA	$ 8,500.00	$ 127,500.00	$ 5,950.00	$ 89,250.00	$ 4,661.72	$ 69,925.80
121	MANHOLES, TYPE J >10'	COJ 202	1	EA	$ 10,000.00	$ 10,000.00	$ 8,200.00	$ 8,200.00	$ 7,191.90	$ 7,191.90
122	MANHOLES, TYPE J PARTIAL, <10'	COJ 202	2	EA	$ 6,500.00	$ 13,000.00	$ 5,950.00	$ 11,900.00	$ 1,809.11	$ 3,618.22
123	DITCH BOTTOM INLETS, TYPE B <10'	COJ 202	1	EA	$ 4,000.00	$ 4,000.00	$ 7,150.00	$ 7,150.00	$ 6,293.62	$ 6,293.62
124	DITCH BOTTOM INLETS, TYPE E <10'	COJ 202	10	EA	$ 4,000.00	$ 40,000.00	$ 5,130.00	$ 51,300.00	$ 2,423.95	$ 24,239.50
125	DITCH BOTTOM INLETS, TYPE E PARTIAL <10'	COJ 202	1	EA	$ 2,000.00	$ 2,000.00	$ 6,100.00	$ 6,100.00	$ 4,378.71	$ 4,378.71
126	CAST IRON TREE GRATE & FRAME		8	EA	$ 1,200.00	$ 9,600.00	$ 2,300.00	$ 18,400.00	$ 3,290.00	$ 26,320.00

STRUCTURES

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
127	REMOVAL OF EXISTING STRUCTURES/BRIDGES (248,640 SF)	FDOT PAY ITEM 110 3	1	LS	$ 3,562,000.00	$ 3,562,000.00	$ 3,540,000.00	$ 3,540,000.00	$ 1,562,225.00	$ 1,562,225.00
128	CONCRETE CLASS NS, GRAVITY WALL	FDOT PAY ITEM 400 0 11	6.7	CY	$ 650.00	$ 4,355.00	$ 1,200.00	$ 8,040.00	$ 2,310.00	$ 15,477.00
129	CONCRETE CLASS II, APPROACH SLABS	FDOT PAY ITEM 400 2 10	150	CY	$ 300.00	$ 45,000.00	$ 500.00	$ 75,000.00	$ 525.00	$ 78,750.00
130	CONCRETE CLASS IV, SUPERSTRUCTURE	FDOT PAY ITEM 400 4 4	398.8	CY	$ 775.00	$ 309,070.00	$ 750.00	$ 299,100.00	$ 997.50	$ 397,803.00
131	CONCRETE CLASS IV, SUBSTRUCTURE	FDOT PAY ITEM 400 4 5	222.2	CY	$ 980.00	$ 217,756.00	$ 800.00	$ 177,760.00	$ 997.50	$ 221,644.50
132	CONCRETE CLAS IV, BULKHEAD	FDOT PAY ITEM 400 4 8	110.9	CY	$ 1,425.00	$ 158,032.50	$ 1,000.00	$ 110,900.00	$ 1,890.00	$ 209,601.00
133	CONCRETE CLASS IV, MASS-SUBSTRUCTURE	FDOT PAY ITEM 400 4 25	229.9	CY	$ 1,450.00	$ 333,355.00	$ 900.00	$ 206,910.00	$ 892.50	$ 205,185.75
134	BRIDGE DECK GROOVING & PLANNING, 8.5" & >	FDOT PAY ITEM 400 9	1336	SY	$ 20.00	$ 26,720.00	$ 7.00	$ 9,352.00	$ 11.55	$ 15,430.80
135	COMPOSITE NEOPRENE PADS	FDOT PAY ITEM 400 147	8.0	CF	$ 1,200.00	$ 9,600.00	$ 2,500.00	$ 20,000.00	$ 3,307.50	$ 26,460.00
136	REINFORCING STEEL, SUPERSTRUCTURE	FDOT PAY ITEM 415 1 14	84726	LB	$ 1.00	$ 84,726.00	$ 0.85	$ 72,017.10	$ 1.10	$ 93,198.60
137	REINFORCING STEEL, SUBSTRUCTURE	FDOT PAY ITEM 415 1 5	74209	LB	$ 1.00	$ 74,209.00	$ 0.85	$ 63,077.65	$ 1.10	$ 81,629.90
138	REINFORCING STEEL, BULKHEAD	FDOT PAY ITEM 415 1 8	9568	LB	$ 1.00	$ 9,568.00	$ 0.85	$ 8,132.80	$ 1.10	$ 10,524.80
139	REINFORCING STEEL, APPROACH SLABS	FDOT PAY ITEM 415 1 9	28686	LB	$ 1.00	$ 28,686.00	$ 0.85	$ 24,383.10	$ 1.10	$ 31,554.60
140	PRESTRESSED BEAMS: AASHTO TYPE II	FDOT PAY ITEM 450 1 1	429	LF	$ 185.00	$ 79,365.00	$ 210.00	$ 90,090.00	$ 341.25	$ 146,396.25
141	PRESTRESSED BEAMS: FLORIDA-I-BEAM 72"	FDOT PAY ITEM 450 2 72	804	LF	$ 444.00	$ 356,976.00	$ 350.00	$ 281,400.00	$ 472.50	$ 379,890.00
142	PRESTRESSED CONCRETE PILING, 24" SQ. (DRIVEN PLUMB)	FDOT PAY ITEM 455 34 5	1624	LF	$ 150.00	$ 243,600.00	$ 144.00	$ 233,856.00	$ 168.00	$ 272,832.00
143	STEEL PILING, HP 12 X 53	FDOT PAY ITEM 455 35 4	624	LF	$ 110.00	$ 68,640.00	$ 122.00	$ 76,128.00	$ 107.10	$ 66,830.40
144	STEEL PILING, HP 14 X 102	FDOT PAY ITEM 455 35 7	752	LF	$ 150.00	$ 112,800.00	$ 140.00	$ 105,280.00	$ 126.00	$ 94,752.00
145	STEEL PILING, HP 16 X 162	FDOT PAY ITEM 455 35 14	329	LF	$ 230.00	$ 75,670.00	$ 269.00	$ 88,501.00	$ 183.75	$ 60,453.75
146	SHEET PILING STEEL, TEMPORARY- CRITICAL	FDOT PAY ITEM 455 133 2	2252	SF	$ 25.00	$ 56,300.00	$ 45.00	$ 101,340.00	$ 39.90	$ 89,854.80
147	SHEET PILING STEEL, FURNISH & INSTALL PERMANENT	FDOT PAY ITEM 455 133 3	13535	LF	$ 55.00	$ 744,425.00	$ 45.00	$ 609,075.00	$ 29.40	$ 397,929.00
148	TEST PILES-PRESTRESSED CONCRETE, 24" SQ.	FDOT PAY ITEM 455 143 5	265	LF	$ 200.00	$ 53,000.00	$ 632.00	$ 167,480.00	$ 315.00	$ 83,475.00
149	TEST PILES- STEEL, HP 12 X 53	FDOT PAY ITEM 455-144-4	60	LF	$ 160.00	$ 9,600.00	$ 988.00	$ 59,280.00	$ 210.00	$ 12,600.00
150	TEST PILES- STEEL, HP 14 X 102	FDOT PAY ITEM 455-144-8	116	LF	$ 280.00	$ 32,480.00	$ 579.00	$ 67,164.00	$ 225.75	$ 26,187.00

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
151	TEST PILES-STEEL, HP 16 X 162	FDOT PAY ITEM 455-144-9	56	LF	$ 295.00	$ 16,520.00	$ 635.00	$ 35,560.00	$ 315.00	$ 17,640.00
152	BRIDGE DECK EXPANSION JOINT, NEW CONST. F&I, POURED JOINT W BACKER ROD	FDOT PAY ITEM 458 1 11	253	LF	$ 20.00	$ 5,060.00	$ 42.00	$ 10,626.00	$ 52.50	$ 13,282.50
153	POLYETHYLENE SHEETING ON CONCRETE PILING	FDOT PAY ITEM 459 71	281	SY	$ 35.00	$ 9,835.00	$ 10.00	$ 2,810.00	$ 7.35	$ 2,065.35
154	STRUCTURAL STEEL, LOW ALLOY	FDOT PAY ITEM 460 2 2	26073	LB	$ 4.00	$ 104,292.00	$ 16.00	$ 417,168.00	$ 16.80	$ 438,026.40
155	BRIDGE DRAIN PIPE	FDOT PAY ITEM 506 2	112	LF	$ 180.00	$ 20,160.00	$ 125.00	$ 14,000.00	$ 157.50	$ 17,640.00
156	BRIDGE DRAINS	FDOT PAY ITEM 506 3	2	EA	$ 1,550.00	$ 3,100.00	$ 2,900.00	$ 5,800.00	$ 6,667.50	$ 13,335.00
157	CONCRETE TRAFFIC RAILING, 36" MEDIAN SINGLE SLOPE	FDOT PAY ITEM 521 5 12	262	LF	$ 100.00	$ 26,200.00	$ 165.00	$ 43,230.00	$ 210.00	$ 55,020.00
158	CONCRETE TRAFFIC RAILING, 36" SINGLE SLOPE	FDOT PAY ITEM 521 5 13	355	LF	$ 110.00	$ 39,050.00	$ 163.00	$ 57,865.00	$ 157.50	$ 55,912.50
159	CONCRETE TRAFFIC RAILING, 42" SINGLE SLOPE	FDOT PAY ITEM 521 5 14	169	LF	$ 120.00	$ 20,280.00	$ 203.00	$ 34,307.00	$ 176.40	$ 29,811.60
160	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, 27" HEIGHT	FDOT PAY ITEM 521 6 32	210	LF	$ 150.00	$ 31,500.00	$ 410.00	$ 86,100.00	$ 495.09	$ 103,968.90
161	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	FDOT PAY ITEM 521 8 7	901	LF	$ 200.00	$ 180,200.00	$ 275.00	$ 247,775.00	$ 370.01	$ 333,379.01
162	CONCRETE BARRIER, WITH JUNCTION SLAB, 42" SINGLE SLOPE	FDOT PAY ITEM 521 8 8	1333	LF	$ 225.00	$ 299,925.00	$ 330.00	$ 439,890.00	$ 480.36	$ 640,319.88
163	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	FDOT PAY ITEM 548 12	49022	SF	$ 40.00	$ 1,960,880.00	$ 34.00	$ 1,666,748.00	$ 51.37	$ 2,518,260.14
164	COATING EXISTING STRUCTURAL STEEL (85.1 TN)	FDOT PAY ITEM 561 1	1	LS	$ 90,000.00	$ 90,000.00	$ 260,000.00	$ 260,000.00	$ 293,851.77	$ 293,851.77
	SIGNING AND PAVEMENT MARKINGS									
165	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	FDOT PAY ITEM 700 1 11	47	AS	$ 348.00	$ 16,356.00	$ 391.00	$ 18,377.00	$ 410.55	$ 19,295.85
166	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	FDOT PAY ITEM 700 1 12	28	AS	$ 1,190.00	$ 33,320.00	$ 1,455.00	$ 40,740.00	$ 1,527.75	$ 42,777.00
167	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	FDOT PAY ITEM 700 1 13	4	AS	$ 1,528.00	$ 6,112.00	$ 1,298.00	$ 5,192.00	$ 1,362.90	$ 5,451.60
168	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	FDOT PAY ITEM 700 1 14	1	AS	$ 2,269.00	$ 2,269.00	$ 1,932.00	$ 1,932.00	$ 2,028.60	$ 2,028.60
169	SINGLE POST SIGN, F&I BARRIER MOUNT, UP TO 12 SF	FDOT PAY ITEM 700 1 21	1	AS	$ 1,555.00	$ 1,555.00	$ 1,720.00	$ 1,720.00	$ 1,806.00	$ 1,806.00
170	SINGLE POST SIGN, F&I BARRIER MOUNT, 12 20 SF	FDOT PAY ITEM 700 1 22	1	AS	$ 1,867.00	$ 1,867.00	$ 1,953.00	$ 1,953.00	$ 2,050.65	$ 2,050.65
171	SINGLE POST SIGN, F&I BRIDGE MOUNT, UP TO 12 SF	FDOT PAY ITEM 700 1 31	6	AS	$ 2,220.00	$ 13,320.00	$ 1,899.00	$ 11,394.00	$ 1,993.95	$ 11,963.70
172	SINGLE POST SIGN, F&I BRIDGE MOUNT, 12 20 SF	FDOT PAY ITEM 700 1 32	2	AS	$ 1,925.00	$ 3,850.00	$ 2,091.00	$ 4,182.00	$ 2,195.55	$ 4,391.10

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
173	SINGLE POST SIGN, F&I BRIDGE MOUNT, 21 30 SF	FDOT PAY ITEM 700 1 33	1	AS	$ 2,500.00	$ 2,500.00	$ 2,509.00	$ 2,509.00	$ 2,634.45	$ 2,634.45
174	SINGLE POST SIGN, RELOCATE	FDOT PAY ITEM 700 1 50	8	AS	$ 250.00	$ 2,000.00	$ 218.00	$ 1,744.00	$ 228.90	$ 1,831.20
175	SINGLE POST SIGN, REMOVE	FDOT PAY ITEM 700 1 60	32	AS	$ 28.00	$ 896.00	$ 20.00	$ 640.00	$ 21.00	$ 672.00
176	SINGLE POST SIGN, F&I CUSTOM, 31+ SF	FDOT PAY ITEM 700 1 74	1	AS	$ 2,700.00	$ 2,700.00	$ 4,206.00	$ 4,206.00	$ 4,416.30	$ 4,416.30
177	MULTI-POST SIGN, F&I GROUND MOUNT, 12 20 SF	FDOT PAY ITEM 700 2 12	2	AS	$ 4,170.00	$ 8,340.00	$ 4,273.00	$ 8,546.00	$ 4,486.65	$ 8,973.30
178	MULTI-POST SIGN, F&I GROUND MOUNT, 31 50 SF	FDOT PAY ITEM 700 2 14	1	AS	$ 4,700.00	$ 4,700.00	$ 5,744.00	$ 5,744.00	$ 6,031.20	$ 6,031.20
179	MULTI-POST SIGN, RELOCATE	FDOT PAY ITEM 700 2 50	2	AS	$ 4,365.00	$ 8,730.00	$ 982.00	$ 1,964.00	$ 1,031.10	$ 2,062.20
180	MULTI-POST SIGN, REMOVE	FDOT PAY ITEM 700 2 60	2	AS	$ 785.00	$ 1,570.00	$ 150.00	$ 300.00	$ 157.50	$ 315.00
181	SIGN PANEL, F&I OVERHEAD MOUNT, 51 100 SF	FDOT PAY ITEM 700 3 205	4	EA	$ 3,300.00	$ 13,200.00	$ 4,215.00	$ 16,860.00	$ 4,425.75	$ 17,703.00
182	SIGN PANEL, F&I OVERHEAD MOUNT, 101 200 SF	FDOT PAY ITEM 700 3 206	10	EA	$ 5,300.00	$ 53,000.00	$ 7,048.00	$ 70,480.00	$ 7,400.40	$ 74,004.00
183	SIGN PANEL, F&I OVERHEAD MOUNT, 201 300 SF	FDOT PAY ITEM 700 3 207	1	EA	$ 8,000.00	$ 8,000.00	$ 5,768.00	$ 5,768.00	$ 6,054.30	$ 6,054.30
184	SIGN PANEL, RELOCATE, 12 20 SF	FDOT PAY ITEM 700 3 502	1	EA	$ 765.00	$ 765.00	$ 320.00	$ 320.00	$ 336.00	$ 336.00
185	SIGN PANEL, REMOVE, UP TO 12 SF	FDOT PAY ITEM 700 3 601	30	EA	$ 50.00	$ 1,500.00	$ 15.00	$ 450.00	$ 15.75	$ 472.50
186	SIGN PANEL, REMOVE, 12 20 SF	FDOT PAY ITEM 700 3 602	1	EA	$ 110.00	$ 110.00	$ 30.00	$ 30.00	$ 31.50	$ 31.50
187	SIGN PANEL, REMOVE, 51 100 SF	FDOT PAY ITEM 700 3 605	2	EA	$ 620.00	$ 1,240.00	$ 150.00	$ 300.00	$ 157.50	$ 315.00
188	SIGN PANEL, REMOVE, 101 200 SF	FDOT PAY ITEM 700 3 606	9	EA	$ 600.00	$ 5,400.00	$ 250.00	$ 2,250.00	$ 262.50	$ 2,362.50
189	SIGN PANEL, REMOVE, 51 100 SF WITH LIGHTING	FDOT PAY ITEM 700 3 625	1	EA	$ 1,300.00	$ 1,300.00	$ 350.00	$ 350.00	$ 367.50	$ 367.50
190	SIGN PANEL, REMOVE, 101 200 SF WITH LIGHTING	FDOT PAY ITEM 700 3 626	1	EA	$ 1,300.00	$ 1,300.00	$ 500.00	$ 500.00	$ 525.00	$ 525.00
191	OVERHEAD STATIC SIGN STRUCTURE, F&I, CANTILEVER, 41 50 FT	FDOT PAY ITEM 700 4 114	2	EA	$ 95,000.00	$ 190,000.00	$ 90,995.00	$ 181,990.00	$ 95,544.75	$ 191,089.50
192	OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN	FDOT PAY ITEM 700 4 620	1	EA	$ 12,000.00	$ 12,000.00	$ 5,900.00	$ 5,900.00	$ 6,195.00	$ 6,195.00
193	ELECTRONIC DISPLAY SIGN, REMOVE- GROUND MOUNT	FDOT PAY ITEM 700 11 600	4	AS	$ 1,000.00	$ 4,000.00	$ 450.00	$ 1,800.00	$ 472.50	$ 1,890.00
194	SIGN BEACON, F&I GROUND MOUNT-SOLAR POWRED, TWO BEACONS	FDOT PAY ITEM 700 12 22	2	AS	$ 7,500.00	$ 15,000.00	$ 5,830.00	$ 11,660.00	$ 6,121.50	$ 12,243.00

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
195	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	FDOT PAY ITEM 700 13 15	8	EA	$ 200.00	$ 1,600.00	$ 85.00	$ 680.00	$ 89.25	$ 714.00
196	OBJECT MARKER, TYPE I	FDOT PAY ITEM 705 10 1	5	EA	$ 225.00	$ 1,125.00	$ 250.00	$ 1,250.00	$ 183.75	$ 918.75
197	DELINEATOR, FLEXIBLE TUBULAR	FDOT PAY ITEM 705 11 1	9	EA	$ 75.00	$ 675.00	$ 250.00	$ 2,250.00	$ 89.25	$ 803.25
198	PAINTED PAVEMENT MARKINGS, STD, YELLOW, ISLAND NOSE	FDOT PAY ITEM 710 11 290	74	SF	$ 2.00	$ 148.00	$ 10.00	$ 740.00	$ 5.25	$ 388.50
199	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	FDOT PAY ITEM 710 90	1	LS	$ 35,000.00	$ 35,000.00	$ 35,000.00	$ 35,000.00	$ 23,625.00	$ 23,625.00
200	THERMO, STD, WHITE, SOLID,12" FOR INTERCHANGE MARKINGS	FDOT PAY ITEM 711 11 103	0.031	GM	$ 7,400.00	$ 229.40	$ 15,840.00	$ 491.04	$ 15,750.00	$ 488.25
201	THERMO, STD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	FDOT PAY ITEM 711 11 123	2453	LF	$ 1.50	$ 3,679.50	$ 3.00	$ 7,359.00	$ 2.10	$ 5,151.30
202	THERMO, STD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	FDOT PAY ITEM 711 11 124	1565	LF	$ 2.25	$ 3,521.25	$ 4.00	$ 6,260.00	$ 2.89	$ 4,522.85
203	THERMO, STD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	FDOT PAY ITEM 711 11 125	785	LF	$ 3.00	$ 2,355.00	$ 5.00	$ 3,925.00	$ 3.41	$ 2,676.85
204	THERMO, STD, WHITE, 2 4 DOTTED GUIDELINE/ 6 10 GAP EXTENSION, 6"	FDOT PAY ITEM 711 11 141	0.193	GM	$ 980.00	$ 189.14	$ 2,500.00	$ 482.50	$ 1,890.00	$ 364.77
205	THERMO, STD, WHITE, MESSAGE OR SYMBOL	FDOT PAY ITEM 711 11 160	36	EA	$ 55.00	$ 1,980.00	$ 125.00	$ 4,500.00	$ 105.00	$ 3,780.00
206	THERMO, STD, WHITE, ARROW	FDOT PAY ITEM 711 11 170	84	EA	$ 45.00	$ 3,780.00	$ 100.00	$ 8,400.00	$ 63.00	$ 5,292.00
207	THERMO, STD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	FDOT PAY ITEM 711 11 224	1987	LF	$ 2.25	$ 4,470.75	$ 4.00	$ 7,948.00	$ 2.89	$ 5,742.43
208	THERMO, STD, YELLOW, 2 4 DOTTED GUIDELINE/6 10 DOTTED EXTENSION LINE, 6"	FDOT PAY ITEM 711 11 241	0.081	GM	$ 920.00	$ 74.52	$ 2,500.00	$ 202.50	$ 1,890.00	$ 153.09
209	THERMO, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	FDOT PAY ITEM 711 14 125	1655	LF	$ 17.00	$ 28,135.00	$ 20.00	$ 33,100.00	$ 12.08	$ 19,992.40
210	THERMO, STD-OTHER SURFACES, WHITE, SOLID, 6"	FDOT PAY ITEM 711 16 101	3.393	GM	$ 4,400.00	$ 14,929.20	$ 5,280.00	$ 17,915.04	$ 3,990.00	$ 13,538.07
211	THERMO, STD-OTHER SURFACES, WHITE, SOLID, 8"	FDOT PAY ITEM 711 16 102	0.279	GM	$ 5,800.00	$ 1,618.20	$ 7,500.00	$ 2,092.50	$ 5,460.00	$ 1,523.34
212	THERMO, STD-OTHER SURFACES, WHITE, SKIP, 6", 10 30 SKIP OR 3 9 LANE DROP	FDOT PAY ITEM 711 16 131	1.395	GM	$ 1,100.00	$ 1,534.50	$ 2,500.00	$ 3,487.50	$ 1,890.00	$ 2,636.55
213	THERMO, STD-OTHER SURFACES, WHITE, SKIP, 12" - APPROACH TO TOLL PLAZA	FDOT PAY ITEM 711 16 133	0.037	GM	$ 1,775.00	$ 65.68	$ 5,000.00	$ 185.00	$ 4,375.95	$ 161.91

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
214	THERMO, STD-OTHER SURFACES, YELLOW, SOLID, 6"	FDOT PAY ITEM 711 16 201	2.219	GM	$ 4,335.00	$ 9,619.37	$ 5,280.00	$ 11,716.32	$ 3,990.00	$ 8,853.81
215	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	FDOT PAY ITEM 713 103 101	0.183	GM	$ 27,200.00	$ 4,977.60	$ 25,000.00	$ 4,575.00	$ 26,250.00	$ 4,803.75
216	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	FDOT PAY ITEM 713 103 131	0.117	GM	$ 6,300.00	$ 737.10	$ 7,500.00	$ 877.50	$ 13,125.04	$ 1,535.63
217	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	FDOT PAY ITEM 713 103 201	0.184	GM	$ 27,100.00	$ 4,986.40	$ 25,000.00	$ 4,600.00	$ 26,250.00	$ 4,830.00
218	PERMANAENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	FDOT PAY ITEM 713 103 331	0.117	GM	$ 6,000.00	$ 702.00	$ 7,500.00	$ 877.50	$ 13,125.04	$ 1,535.63
				SIGNALIZATION						
219	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	FDOT PAY ITEM 630 2 11	961	LF	$ 9.00	$ 8,649.00	$ 7.50	$ 7,207.50	$ 8.40	$ 8,072.40
220	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	FDOT PAY ITEM 630 2 12	5640	LF	$ 31.00	$ 174,840.00	$ 21.50	$ 121,260.00	$ 31.50	$ 177,660.00
221	SIGNAL CABLE- NEW OR RECON INTERSECTION, F&I	FDOT PAY ITEM 632 7 1	7	PI	$ 4,200.00	$ 29,400.00	$ 3,985.00	$ 27,895.00	$ 4,200.00	$ 29,400.00
222	SIGNAL CABLE, REMOVE-INTERSECTION	FDOT PAY ITEM 632 7 6	10	PI	$ 525.00	$ 5,250.00	$ 450.00	$ 4,500.00	$ 525.00	$ 5,250.00
223	FIBER OPTIC CABLE, F&I, UNDERGROUND, 2 12	FDOT PAY ITEM 633 1 121	67	LF	$ 3.00	$ 201.00	$ 3.00	$ 201.00	$ 2.63	$ 176.21
224	FIBER OPTIC CABLE, F&I, UNDERGROUND, 13 48 FIBERS	FDOT PAY ITEM 633 1 122	2056	LF	$ 3.00	$ 6,168.00	$ 3.50	$ 7,196.00	$ 2.63	$ 5,407.28
225	FIBER OPTIC CABLE, F&I, UNDERGROUND, 49 96 FIBERS	FDOT PAY ITEM 633 1 123	5665	LF	$ 3.00	$ 16,995.00	$ 3.00	$ 16,995.00	$ 2.89	$ 16,371.85
226	FIBER OPTIC CONNECTION, INSTALL, SPLICE	FDOT PAY ITEM 633 2 31	396	EA	$ 42.00	$ 16,632.00	$ 40.00	$ 15,840.00	$ 42.00	$ 16,632.00
227	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	FDOT 633 2 32	432	EA	$ 78.00	$ 33,696.00	$ 72.50	$ 31,320.00	$ 78.75	$ 34,020.00
228	FIBER OPTIC CONNECTION HDWR, F&I, SPLICE ENCLOSURE	FDOT PAY ITEM 633 3 11	9	EA	$ 840.00	$ 7,560.00	$ 815.00	$ 7,335.00	$ 840.00	$ 7,560.00
229	FIBER OPTIC CONNECTION HDWR, F&I, SPLICE TRAY	FDOT PAY ITEM 633 3 12	33	EA	$ 63.00	$ 2,079.00	$ 60.00	$ 1,980.00	$ 63.00	$ 2,079.00
230	FIBER OPTIC CONN HDWR, F&I, BUFFER TUBE FAN OUT KIT	FDOT PAY ITEM 633 3 14	33	EA	$ 78.00	$ 2,574.00	$ 75.00	$ 2,475.00	$ 78.75	$ 2,598.75
231	FIBER OPTIC CONN HDWR, F&I, PATCH PANEL-FIELD TERM	FDOT PAY ITEM 633 3 16	18	EA	$ 2,517.00	$ 45,306.00	$ 2,215.00	$ 39,870.00	$ 2,520.00	$ 45,360.00
232	MULTI-CONDUCTOR COMMUNICATION CABLE, REMOVE	FDOT PAY ITEM 633 8 6	5220	LF	$ 0.27	$ 1,409.40	$ 0.50	$ 2,610.00	$ 0.26	$ 1,357.20

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
233	PULL & SPLICE BOX, F&I, 13" X 24" COVER SIZE	FDOT PAY ITEM 635 2 11	43	EA	$ 352.00	$ 15,136.00	$ 695.00	$ 29,885.00	$ 351.75	$ 15,125.25
234	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	FDOT PAY ITEM 635 2 12	13	EA	$ 997.00	$ 12,961.00	$ 1,295.00	$ 16,835.00	$ 997.50	$ 12,967.50
235	PULL & SPLICE BOX, INSTALL	FDOT PAY ITEM 635 2 30	4	EA	$ 262.00	$ 1,048.00	$ 595.00	$ 2,380.00	$ 262.50	$ 1,050.00
236	ELECTRICAL POWER SERVICE, F&I, UG, METER NOT REQ	FDOT PAY ITEM 639 1 123	7	AS	$ 3,146.00	$ 22,022.00	$ 1,395.00	$ 9,765.00	$ 3,150.00	$ 22,050.00
237	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	FDOT PAY ITEM 639 1 620	8	AS	$ 157.00	$ 1,256.00	$ 1,395.00	$ 11,160.00	$ 157.50	$ 1,260.00
238	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	FDOT PAY ITEM 639 2 1	1869	LF	$ 4.20	$ 7,849.80	$ 3.65	$ 6,821.85	$ 4.20	$ 7,849.80
239	ELECTRICAL SERVICE WIRE, REMOVE	FDOT PAY ITEM 639 2 6	1775	LF	$ 0.32	$ 568.00	$ 0.50	$ 887.50	$ 0.32	$ 568.00
240	PRESTRESSED CNC POLE, F&I, TYPE P-II SERVICE POLE	FDOT PAY ITEM 641 2 12	7	EA	$ 1,100.00	$ 7,700.00	$ 1,150.00	$ 8,050.00	$ 1,050.00	$ 7,350.00
241	ALUMINUM SIGNALS POLE, PEDESTAL	FDOT PAY ITEM 646 1 11	18	EA	$ 2,000.00	$ 36,000.00	$ 1,295.00	$ 23,310.00	$ 1,995.00	$ 35,910.00
242	ALUMINUM SIGNALS POLE, REMOVE	FDOT PAY ITEM 646 1 60	2	EA	$ 210.00	$ 420.00	$ 150.00	$ 300.00	$ 210.00	$ 420.00
243	STEEL MAST ARM ASSEMBLY, F&I, SINGLE ARM 40'	FDOT PAY ITEM 649 21 3	2	EA	$ 45,000.00	$ 90,000.00	$ 42,000.00	$ 84,000.00	$ 44,625.00	$ 89,250.00
244	STEEL MAST ARM ASSEMBLY, F&I, SINGLE ARM 50'	FDOT PAY ITEM 649 21 6	4	EA	$ 50,000.00	$ 200,000.00	$ 40,000.00	$ 160,000.00	$ 49,875.00	$ 199,500.00
245	STEEL MAST ARM ASSEMBLY, F&I, SINGLE ARM 60'	FDOT PAY ITEM 649 21 10	2	EA	$ 60,000.00	$ 120,000.00	$ 73,000.00	$ 146,000.00	$ 59,850.00	$ 119,700.00
246	STEEL MAST ARM ASSEMBLY, F&I, SINGLE ARM 70'	FDOT PAY ITEM 649 21 15	1	EA	$ 70,000.00	$ 70,000.00	$ 48,500.00	$ 48,500.00	$ 67,725.00	$ 67,725.00
247	STEEL MAST ARM ASSEMBLY, F&I, DOUBLE ARM 70'-40'	FDOT PAY ITEM 649 21 17	1	EA	$ 75,000.00	$ 75,000.00	$ 60,500.00	$ 60,500.00	$ 72,450.00	$ 72,450.00
248	STEEL MAST ARM ASSEMBLY, F&I, DOUBLE ARM 78'-50'	FDOT PAY ITEM 649 21 24	1	EA	$ 85,000.00	$ 85,000.00	$ 74,000.00	$ 74,000.00	$ 85,050.00	$ 85,050.00
249	STEEL MAST ARM ASSEMBLY, F&I, DOUBLE ARM 78'-78'	FDOT PAY ITEM 649 21 27	1	EA	$ 95,000.00	$ 95,000.00	$ 105,000.00	$ 105,000.00	$ 92,400.00	$ 92,400.00
250	STEEL MAST ARM ASSEMBLY, F&I, DEEP FDN-BOLT ON ATTACH	FDOT PAY ITEM 649 26 5	14	EA	$ 12,200.00	$ 170,800.00	$ 8,520.00	$ 119,280.00	$ 12,075.00	$ 169,050.00
251	VEH TRAFFIC SIGNAL, F&I ALUMINUM, SECTION 1 WAY	FDOT PAY ITEM 650 1 11	2	AS	$ 630.00	$ 1,260.00	$ 752.00	$ 1,504.00	$ 630.00	$ 1,260.00
252	VEH TRAFFIC SIGNAL, F&I ALUMINUM, 3 SECTION 1 WAY	FDOT PAY ITEM 650 1 14	39	AS	$ 1,000.00	$ 39,000.00	$ 1,000.00	$ 39,000.00	$ 997.50	$ 38,902.50
253	PEDESTRIAN SIGNAL, F&I LED COUNTDOWN, 1 WAY	FDOT PAY ITEM 653 1 11	18	AS	$ 630.00	$ 11,340.00	$ 550.00	$ 9,900.00	$ 630.00	$ 11,340.00

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
254	VEHICLE DETECTION SYSTEM-MICRO, F&I CABINET EQUIP	FDOT PAY ITEM 660 3 11	7	EA	$ 4,200.00	$ 29,400.00	$ 5,250.00	$ 36,750.00	$ 4,200.00	$ 29,400.00
255	VEHICLE DETECTION SYSTEM-MICRO, F&I ABO EQUIP	FDOT PAY ITEM 660 3 12	18	EA	$ 7,000.00	$ 126,000.00	$ 8,800.00	$ 158,400.00	$ 7,035.00	$ 126,630.00
256	VEHICLE DETECTION SYSTEM-AVI, BT, F&I, CABINET EQUIP	FDOT PAY ITEM 660 6 121	7	EA	$ 4,725.00	$ 33,075.00	$ 675.00	$ 4,725.00	$ 4,725.00	$ 33,075.00
257	VEHICLE DETECTION SYSTEM-AVI, BT, F&I, ABO EQUIP	FDOT PAY ITEM 660 6 122	7	EA	$ 4,200.00	$ 29,400.00	$ 8,275.00	$ 57,925.00	$ 4,200.00	$ 29,400.00
258	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	FDOT PAY ITEM 665 1 11	18	EA	$ 210.00	$ 3,780.00	$ 270.00	$ 4,860.00	$ 210.00	$ 3,780.00
259	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	FDOT PAY ITEM 670 5 110	7	AS	$ 28,400.00	$ 198,800.00	$ 28,000.00	$ 196,000.00	$ 28,350.00	$ 198,450.00
260	TRAF CNTL ASSEM, REMOVE CONTROLLER WITH CABINET	FDOT PAY ITEM 670 5 500	11	AS	$ 370.00	$ 4,070.00	$ 450.00	$ 4,950.00	$ 367.50	$ 4,042.50
261	ITS CCTV CAMERA, F&I, DOME ENCL- NP, IP, HIGH DEF	FDOT PAY ITEM 682 1 133	5	EA	$ 9,000.00	$ 45,000.00	$ 7,000.00	$ 35,000.00	$ 8,925.00	$ 44,625.00
262	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	FDOT PAY ITEM 684 1 1	7	EA	$ 3,500.00	$ 24,500.00	$ 2,570.00	$ 17,990.00	$ 3,465.00	$ 24,255.00
263	MEDIA CONVERTER, FURNISH & INSTALL	FDOT PAY ITEM 684 5 1	2	EA	$ 1,155.00	$ 2,310.00	$ 870.00	$ 1,740.00	$ 1,155.00	$ 2,310.00
264	UNITERRUPTIBLE POWER SUPPLY, F&I, LINE INTERACTIVE	FDOT PAY ITEM 685 1 11	7	EA	$ 5,245.00	$ 36,715.00	$ 3,950.00	$ 27,650.00	$ 5,250.00	$ 36,750.00
265	SIGN PANEL, F&I OVERHEAD MOUNT, UP TO 12 SF	FDOT PAY ITEM 700 2 201	20	EA	$ 630.00	$ 12,600.00	$ 595.00	$ 11,900.00	$ 630.00	$ 12,600.00
266	INTERNAL ILLUM SIGN, F&I, OM, 12 18 SF, DOUBLE-SIDED	FDOT PAY ITEM 700 5 22	8	EA	$ 3,150.00	$ 25,200.00	$ 3,900.00	$ 31,200.00	$ 3,150.00	$ 25,200.00
267	ELE DIS SIGN, F&I OM-AC-P, BLANK OUT SIGN, UP TO 12 SF	FDOT PAY ITEM 700 11 391	1	AS	$ 5,455.00	$ 5,455.00	$ 3,660.00	$ 3,660.00	$ 5,460.00	$ 5,460.00
				LIGHTING						
268	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	FDOT PAY ITEM 630 2 11	5260	LF	$ 8.00	$ 42,080.00	$ 7.50	$ 39,450.00	$ 7.88	$ 41,448.80
269	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	FDOT PAY ITEM 630 2 12	4461	LF	$ 30.00	$ 133,830.00	$ 21.50	$ 95,911.50	$ 29.40	$ 131,153.40
270	PULL & SPLICE BOX, F&I, 13" X 24" COVER SIZE	FDOT PAY ITEM 635 2 11	6	EA	$ 370.00	$ 2,220.00	$ 795.00	$ 4,770.00	$ 367.50	$ 2,205.00
271	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 TO 000)	FDOT PAY ITEM 715 1 15	8679	LF	$ 2.65	$ 22,999.35	$ 4.00	$ 34,716.00	$ 2.63	$ 22,825.77
272	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTORS OWN	FDOT PAY ITEM 715 1 60	4806	LF	$ 0.30	$ 1,441.80	$ 0.35	$ 1,682.10	$ 0.26	$ 1,249.56

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
273	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDRARD POLE SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	FDOT PAY ITEM 715 4 21	17	EA	$ 7,700.00	$ 130,900.00	$ 7,875.00	$ 133,875.00	$ 7,685.00	$ 130,305.00
274	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	FDOT PAY ITEM 715 4 70	34	EA	$ 685.00	$ 23,290.00	$ 350.00	$ 11,900.00	$ 682.50	$ 23,205.00
275	LOAD CENTER, F&I, SECONDARY VOLTAGE	FDOT PAY ITEM 715 7 11	4	EA	$ 20,000.00	$ 80,000.00	$ 9,865.00	$ 39,460.00	$ 19,950.00	$ 79,800.00
276	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	FDOT PAY ITEM 715 11 211	4	EA	$ 2,000.00	$ 8,000.00	$ 985.00	$ 3,940.00	$ 1,785.00	$ 7,140.00
277	LUMINAIRE, REMOVE	FDOT PAY ITEM 715 11 500	12	EA	$ 185.00	$ 2,220.00	$ 65.00	$ 780.00	$ 183.75	$ 2,205.00
278	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	FDOT PAY ITEM 715 500 1	21	EA	$ 475.00	$ 9,975.00	$ 395.00	$ 8,295.00	$ 472.50	$ 9,922.50
279	ALUMINUM POLE W/SINGLE DECORATIVE ACORN 100W LED FIXTURE	JEA LDA01*14	1	EA	$ 12,000.00	$ 12,000.00	$ 9,985.00	$ 9,985.00	$ 11,550.00	$ 11,550.00
280	LED DOUBLE DECORATIVE ACORN PEDESTRIAN LIGHT	JEA LDDA01	90	EA	$ 12,000.00	$ 1,080,000.00	$ 11,596.00	$ 1,043,640.00	$ 11,550.00	$ 1,039,500.00
281	115 WATT, LED, 27' ALUMINUM POLE, SINGLE COBRA FIXTURE/WALL MOUNTED	JEA L1601T	2	EA	$ 5,250.00	$ 10,500.00	$ 5,106.00	$ 10,212.00	$ 5,250.00	$ 10,500.00
282	115 WATT, LED 27' ALUMINUM POLE, DOUBLE CORBA FIXTURE/WALL MOUNTED	JEA L1601DT	4	EA	$ 6,100.00	$ 24,400.00	$ 5,537.00	$ 22,148.00	$ 6,090.00	$ 24,360.00
283	LUMINAIRE RETRO-FIT KIT TO LED	JEA LDA01* RETRO	13	EA	$ 2,425.00	$ 31,525.00	$ 750.00	$ 9,750.00	$ 2,415.00	$ 31,395.00
284	LIGHT POLE ANCHOR BASE FOR JEA PLATE LDDA01 AND LAD01*4	JEA ANCBASE6	91	EA	$ 2,000.00	$ 182,000.00	$ 1,000.00	$ 91,000.00	$ 1,995.00	$ 181,545.00
285	LIGHT POLE ANCHOR BASE FOR 30' POLE JEA PLATES POLAL010 AND STLLE005	JEA ANCBASE2	12	EA	$ 2,200.00	$ 26,400.00	$ 1,000.00	$ 12,000.00	$ 2,205.00	$ 26,460.00
286	BOX, SPLICE, HEAVY DUTY CONCRETE, (HS-20-LOAD), INSIDE 16" X 24"LX24"D, COVER READS ELECTRIC	JEA BOX SP 002	111	EA	$ 1,100.00	$ 122,100.00	$ 895.00	$ 99,345.00	$ 1,050.00	$ 116,550.00
287	LUMINAIRE, 144W LED, SHOEBOX, 120 VAC	JEA STLLE 005	12	EA	$ 1,575.00	$ 18,900.00	$ 2,496.00	$ 29,952.00	$ 1,575.00	$ 18,900.00
288	POLE, ROUND ALUMINUM, 35' IN LENGTH, BASE SLOTTED FOR 4-1" ANCHOR BOLTS, FOR SHOEBOX LUMINAIRE	JEA POLAL010	12	EA	$ 3,700.00	$ 44,400.00	$ 6,495.00	$ 77,940.00	$ 3,675.00	$ 44,100.00
289	115W LED FIXTURE, WITHOUT BRACKET	JEA L201R	8	EA	$ 2,310.00	$ 18,480.00	$ 595.00	$ 4,760.00	$ 2,310.00	$ 18,480.00
290	ELBOW, PVC, CONDUIT, 1", 90-DEGREE, 36" SWEEP-RADIUS, SCH 40	JEA COD EP 004	117	EA	$ 13.00	$ 1,521.00	$ 19.00	$ 2,223.00	$ 12.60	$ 1,474.20
291	CONDUIT, PVC, 1" W/COUPLING ATTACHED OR ONE BELLED END	JEA COD PC 020	515	LF	$ 11.00	$ 5,665.00	$ 5.00	$ 2,575.00	$ 10.50	$ 5,407.50
	TOTAL PART A BID (ITEM NOS. 1-291)				**$ 30,336,731.35**		**$ 31,385,326.82**		**$ 25,456,249.15**	

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
	PART B-POTABLE WATER									
292	6" PVCP DR-18	801.XIII.1	81	LF	$ 20.00	$ 1,620.00	$ 116.00	$ 9,396.00	$ 50.20	$ 4,066.20
293	6" X12" TEE- DI MJ	801.XIII.2	1	EA	$ 450.00	$ 450.00	$ 191.00	$ 191.00	$ 913.66	$ 913.66
294	6" GATE VALVE AND BOX- DI MJ	801.XIV.3	1	EA	$ 950.00	$ 950.00	$ 1,210.00	$ 1,210.00	$ 1,108.47	$ 1,108.47
295	8" PVCP DR-18	801.XIII.1	53	LF	$ 25.00	$ 1,325.00	$ 233.00	$ 12,349.00	$ 76.07	$ 4,031.71
296	CUT AND REMOVE 8" PIPE	801.III.2.4	8	LF	$ 100.00	$ 800.00	$ 266.00	$ 2,128.00	$ 64.94	$ 519.52
297	CUT CAP 8" PIPE	801.III.2.2	3	EA	$ 650.00	$ 1,950.00	$ 1,400.00	$ 4,200.00	$ 413.01	$ 1,239.03
298	8" SOLID SLEEVE CONNECTION	801.XIV.7	2	EA	$ 1,500.00	$ 3,000.00	$ 3,920.00	$ 7,840.00	$ 400.97	$ 801.94
299	8" 45 DEGREE BEND- DI MJ	801.XIII.2	4	EA	$ 450.00	$ 1,800.00	$ 1,071.00	$ 4,284.00	$ 430.10	$ 1,720.40
300	8" GATE VALVE AND BOX- DI MJ	801.XIV.3	2	EA	$ 1,250.00	$ 2,500.00	$ 1,895.00	$ 3,790.00	$ 1,527.57	$ 3,055.14
301	8"X12" REDUCER- DI MJ	801.XIII.2	1	EA	$ 450.00	$ 450.00	$ 890.00	$ 890.00	$ 542.12	$ 542.12
302	8"X12" TEE- DI MJ	801.XIII.2	1	EA	$ 1,500.00	$ 1,500.00	$ 1,290.00	$ 1,290.00	$ 953.75	$ 953.75
303	12" PVCP DR-18	801.XIII.1	704	LF	$ 30.00	$ 21,120.00	$ 111.00	$ 78,144.00	$ 40.07	$ 28,209.28
304	12" DIP CL350	801.XIII.1	142	LF	$ 45.00	$ 6,390.00	$ 206.00	$ 29,252.00	$ 83.10	$ 11,800.20
305	12" SOLID SLEEVE CONNECTION- DI MJ	801.XIV.7	1	EA	$ 2,000.00	$ 2,000.00	$ 4,203.00	$ 4,203.00	$ 570.67	$ 570.67
306	12" 11 1/4 DEGREE BEND- DI MJ	801.XIII.2	1	EA	$ 2,000.00	$ 2,000.00	$ 1,150.00	$ 1,150.00	$ 717.74	$ 717.74
307	12" 45 DEGREE BEND- DI MJ	801.XIII.2	6	EA	$ 2,000.00	$ 12,000.00	$ 1,433.00	$ 8,598.00	$ 746.68	$ 4,480.08
308	12" X 12" TEE- DI MJ	801.XIII.1	1	EA	$ 2,500.00	$ 2,500.00	$ 1,511.00	$ 1,511.00	$ 1,148.66	$ 1,148.66
309	12" GATE VALVE AND BOX- DI MJ	801.XIV.3	3	EA	$ 3,500.00	$ 10,500.00	$ 2,849.00	$ 8,547.00	$ 2,718.15	$ 8,154.45

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
310	FIRE HYDRANT- DI MJ	801.XIV.I	2	EA	$ 2,000.00	$ 4,000.00	$ 3,313.00	$ 6,626.00	$ 3,206.89	$ 6,413.78
311	TEMPORARY SAMPLE TAPS	801.XIII.12	3	EA	$ 450.00	$ 1,350.00	$ 455.00	$ 1,365.00	$ 324.98	$ 974.94
312	GROUT FILL 8" WATER MAIN	801.III.2.3	615	LF	$ 5.00	$ 3,075.00	$ 30.00	$ 18,450.00	$ 4.74	$ 2,915.10
313	FIRE HYDRANT REMOVAL	801.III.3	2	LS	$ 250.00	$ 500.00	$ 1,025.00	$ 2,050.00	$ 1,095.31	$ 2,190.62
314	12" PIPE JOINT RESTRAINTS	801.XIII.6	42	EA	$ 450.00	$ 18,900.00	$ 294.00	$ 12,348.00	$ 498.33	$ 20,929.86
315	6" PIPE JOINT RESTRAINTS	801.XIII.6	4	EA	$ 150.00	$ 600.00	$ 180.00	$ 720.00	$ 91.21	$ 364.84
316	8" PIPE JOINT RESTRAINTS	801.XIII.6	3	EA	$ 250.00	$ 750.00	$ 213.00	$ 639.00	$ 124.60	$ 373.80
317	16" PVCP DR-18	801.XIII.1	41	LF	$ 100.00	$ 4,100.00	$ 190.00	$ 7,790.00	$ 142.25	$ 5,832.25
318	16" 45 DEGREE BEND - DI MJ	801.XIII.2	4	EA	$ 2,500.00	$ 10,000.00	$ 2,360.00	$ 9,440.00	$ 1,354.71	$ 5,418.84
319	CUT AND REMOVE 16" PVC WM	801.III.2.4	18	LF	$ 250.00	$ 4,500.00	$ 230.00	$ 4,140.00	$ 49.98	$ 899.64
320	16" SOLID SLEEVE CONNECTION- DI MJ	801.XIV.7	1	EA	$ 3,000.00	$ 3,000.00	$ 4,965.00	$ 4,965.00	$ 1,080.68	$ 1,080.68
	TOTAL PART B BID (ITEM NOS. 292-320)				**$ 123,630.00**		**$ 247,506.00**		**$ 121,427.37**	
	PART C- POTABLE WATER									
321	12" SOLID SLEEVE CONNECTION- DI MJ	801.XIV.7	2	EA	$ 2,000.00	$ 4,000.00	$ 4,210.00	$ 8,420.00	$ 570.69	$ 1,141.38
322	12" X12" TEE -DI MJ	801.XII.2	2	EA	$ 2,500.00	$ 5,000.00	$ 1,535.00	$ 3,070.00	$ 1,148.61	$ 2,297.22
323	12" GATE VALVE AND BOX- DI MJ	801.XIV.3	3	EA	$ 3,500.00	$ 10,500.00	$ 2,850.00	$ 8,550.00	$ 2,718.15	$ 8,154.45
324	12"X16" REDUCER- DI MJ	801.XIII.2	2	EA	$ 2,000.00	$ 4,000.00	$ 1,385.00	$ 2,770.00	$ 990.85	$ 1,981.70
325	16" DIP CL350	801.XIII.I	1067	LF	$ 125.00	$ 133,375.00	$ 169.00	$ 180,323.00	$ 90.88	$ 96,968.96
326	16" PVCP DR-18	801.XIII.I	903	LF	$ 100.00	$ 90,300.00	$ 128.00	$ 115,584.00	$ 61.41	$ 55,453.23
327	16" SOLID SLEEVE CONNECTION- DI MJ	801.XIV.7	1	EA	$ 3,000.00	$ 3,000.00	$ 4,970.00	$ 4,970.00	$ 1,080.68	$ 1,080.68

TITLE:	URBAN CORE RIVERFRONT REVITALIZATION & COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR				JOHNSON BROS CORPORATION, A SOUTHLAND COMPANY		SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		J.B. COXWELL CONTRACTING, INC.	
BID NO.	CF-0043-20 (PW)									
328	16" 11 1/4 DEGREE BEND- DI MJ	801.XIII.2	4	EA	$ 2,500.00	$ 10,000.00	$ 1,755.00	$ 7,020.00	$ 1,358.16	$ 5,432.64
329	16" 22 1/2 DEGREE BEND- DI MJ	801.XIII.2	2	EA	$ 2,500.00	$ 5,000.00	$ 1,698.00	$ 3,396.00	$ 1,287.34	$ 2,574.68
330	16" 45 DEGREE BEND - DI MJ	801.XIII.2	22	EA	$ 2,500.00	$ 55,000.00	$ 2,294.00	$ 50,468.00	$ 1,354.71	$ 29,803.62
331	16" 90 DEGREE BEND- DI MJ	801.XIII.2	4	EA	$ 2,500.00	$ 10,000.00	$ 2,051.00	$ 8,204.00	$ 1,491.46	$ 5,965.84
332	16"X16" TEE-DI MJ	801.XIII.2	2	EA	$ 3,000.00	$ 6,000.00	$ 3,031.00	$ 6,062.00	$ 2,135.73	$ 4,271.46
333	16" GATE VALVE AND BOX- DI MJ	801.XIV.3	3	EA	$ 4,000.00	$ 12,000.00	$ 6,091.00	$ 18,273.00	$ 6,218.87	$ 18,656.61
334	TEMPORARY SAMPLE TAPS	801.XIII.12	5	EA	$ 450.00	$ 2,250.00	$ 443.00	$ 2,215.00	$ 324.99	$ 1,624.95
335	16" PIPE JOINT RESTRAINTS	801.XIII.6	35	EA	$ 550.00	$ 19,250.00	$ 500.00	$ 17,500.00	$ 751.88	$ 26,315.80
336	SPECIFIED IMPORTED ROADWAY EMBANKMENT FOR BEDDING/BACKFILL	801.IV.5	560	CY	$ 35.00	$ 19,600.00	$ 100.00	$ 56,000.00	$ 12.68	$ 7,100.80
	TOTAL PART C BID (ITEM NOS. 321-336)				$ 389,275.00		$ 492,825.00		$ 268,824.02	
	TOTAL BASE BID SUM PARTS A +B+C				$ 30,849,636.35		$ 32,125,657.82		$ 25,846,500.54	
					PRICING CORRECTED		**PRICING CORRECTED**			
					NOT PRE-QUALIFIED WITH CITY IN THE HORIZONTAL CATEGORY PER ITB*					
	CONFLICT OF INTEREST:				YES		YES		YES	
	BID BOND:				YES		YES		YES	
	STATE FORMS:				YES		YES		YES	
	LICENSED SUBS:				YES		YES		YES	
	ADDENDUMS (1,2,3,4,5,6,7,8,9) ACKNOWLEDGED:				YES		YES		YES	

B. **BASIS OF AWARD**

The project will be awarded to the lowest responsive, responsible Bidder, unless the CITY rejects all bids. The sum total of the PART A, PART B, and PART C bids will be used to determine the lowest bidder, contingent on the availability of funds within the project's approved budget. The CITY has the right to reject any or all bids, with cause.

C. **REVISIONS OF BID PROPOSAL FORM**

Request for revision of the Bid Proposal Form must be made to the ENGINEER at least three (3) days prior to date of opening of Bids. Revision of the Bid Proposal by the Bidder will void the Bid.

D. **CONTRACT EXPIRATION DATE**

The Contract expiration date shall be established as follows:

The notice to proceed date plus ten (10) calendar days for mobilization, plus the construction time established in the Proposal, plus time extensions pursuant to valid change orders (which shall establish the construction completion date), plus 120 days to assure a contract exists beyond the scheduled construction completion date in order to comply with Executive Order Number 13-05.

E. **BID CHANGES**

No changes in the amount of Bids appearing on the outside of Bids will be considered. Only the amounts shown on bidding documents inside the envelope will be considered. All changes, corrections and erasures must be initialed by the person signing the bid.

F. **CONSTRUCTION COMPLETION**

The CONTRACTOR shall begin work within ten (10) calendar days, including Sundays and holidays, after the date of written notice from the owner to begin work, and shall complete PART A, PART B, and PART C of the Base Bid work within **720** calendar days including Sundays and holidays, after the expiration of such ten (10) day notice. If the Bidder determines that "off-hours" work is anticipated to complete the project within such allotted times, a schedule therefore shall be attached to this proposal as required by Section 20.3.4 of the General Conditions.

G. **BID SECURITY**

A Certified Check on _____ (or) Cashier's Check on _____ (or) Bid Bond properly executed by the undersigned and by qualified surety in the sum of _____ representing not less than five percent (5%) of the total amount of the PART A Base Bid, made payable to the Tax Collector, City of Jacksonville, Florida, which the undersigned Bidder hereby deposits as a guarantee of good faith and which it agrees to forfeit to the CITY of Jacksonville, not as a penalty, but as fixed and liquidated damages in the event it fails to enter into Contract, or fail to furnish the contract bond required in accordance with the Special Conditions within ten (10) days after receipt of the contract.

URBAN CORE RIVERFRONT REVITALIZATION AND COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR
SECTION 30

SCOPE OF WORK

30.1 PART A Scope The work covered by the PART A plans and specifications consists of furnishing all labor, materials and equipment; and performing all operations necessary for the construction of **URBAN CORE RIVERFRONT REVITALIZATION AND COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR**, as specified in the Contract Documents.

30.2 PART B Scope The work covered by the PART B plans and specifications consists of furnishing all labor, materials and equipment; and performing all operations necessary for the construction of **JEA potable water main improvements**, as specified in the Contract Documents.

30.3 PART C Scope The work covered by the PART C plans and specifications consists of furnishing all labor, materials and equipment; and performing all operations necessary for the construction of **JEA potable water main improvements**, as specified in the Contract Documents.

30.4 Location This project is located within the limits of the City of Jacksonville, Florida. The construction area is approximately along the Hart Bridge Expressway between Lafayette Street and Gator Bowl Boulevard.

30.5 Intent It is the intent of these Contract Documents to construct the **URBAN CORE RIVERFRONT REVITALIZATION AND COMPLETE STREETS: HART BRIDGE EXPRESSWAY & TALLEYRAND CONNECTOR** project as shown on the plans and including but not limited to:

PART A:

1. Roadway
2. Structures
3. Removal of Existing Structures
4. Drainage
5. Temporary Traffic Control
6. Signing & Pavement Marking
7. Signalization
8. Lighting

PART B:

1. Potable Water

PART C:

1. Potable Water

It is not the intent of these Contract Documents to minutely define the mode and fabric of construction of this project, but rather to set forth reasonable and rational criteria for the construction thereof.