**SUBJECT: GASKINS ROAD EMBANKMENT REPAIR PROJECT**

**BID #: JCF-0011-21** **OPEN DATE:** 2020-10-07

**GENERAL GOVERNMENT AWARDS COMMITTEE**

**KIND AND BASIS OF CONTRACT: CONSTRUCTION FIXED-JSEB SET-ASIDE**

**AGENCY: PUBLIC WORKS**

**BASIS OF AWARD: TOTAL BASE BID, PLUS SELECTED ALTERNATES (IF ANY)-LOWEST RESPONSIVE, RESPONSIBLE BIDDER**

**NUMBER OF BIDS INVITED:** (13) **NUMBER RECEIVED**: (6) **OTHER** (1)

**SUMMARY OF BIDS AND RECOMMENDED ACTIONS:**
Recommend approval of award to ONAS Corporation, as the lowest responsive, responsible bidder in the total base bid amount of $236,475.00.

This award is to be funded by account(s): 009030-565050-1-44102-381920 to be executed by formal contract through Office of General Counsel.

Attachments: Recommendation Memo, Bid Tabulation Sheet, JSEB Letter, Basis of Award, Scope of Work

**ANALYST:** _____ MARILYN LAIDLER **RESPECTFULLY SUBMITTED** _____ GREGORY PEASE, CHIEF PROCUREMENT DIVISION

**CONCURRENCE BY: Robin G. Smith P.E., Chief, Engineering & Construction Management**

**(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)**
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

**ACTION OF AWARDING AUTHORITY** DATE _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

# City of Jacksonville, Florida

*Lenny Curry, Mayor*

Department of Public Works
214 N. Hogan St., 10th floor
Jacksonville, FL 32202
(904) 255-8786
www.coj.net

ONE CITY. ONE JACKSONVILLE

November 4, 2020

TO: Gregory W. Pease
Chief of Procurement

THRU: John P. Pappas, P.E.
Director

FROM: Robin G. Smith, P. E.
Chief, Engineering & Construction Management

SUBJECT: RECOMMENDATION TO AWARD

RE: Gaskins Road Embankment Repair
Bid No.: JCF-0011-21
Bid Date: October 7, 2020
Award Amount: $236,475.00

The Department of Public Works has tabulated and reviewed the six (6) bids received on the referenced project for accuracy and compliance with the contract documents. The apparent low bid by ONAS Corporation has also been reviewed by the EBO Office who has determined that the bidder is in compliance with the set-aside JSEB requirements established for this project. In addition, Public Works has confirmed through www.myfloridalicense.com the appropriate licenses for this contractor and listed subcontractors, if applicable.

We therefore recommend that award of the Total Base Bid for Gaskins Road Embankment Repair Project be awarded to ONAS Corporation, 2050 University Blvd. N., Jacksonville, Florida 32211, in accordance with the attached bid documents in the amount of $236,475.00.

Funding for this project should be as follows:

| ACCOUNTS: | TOTAL |
|---|---|
| 009030 | |
| PWEN DSR Capital Improvements - Flood Control Stormwater Management | |
| 565050 | |
| 1 | |
| 44102-381920 | |
| $236,475.00 | $236,475.00 |

RGS/lw

Attachments

cc: Lori West, Engineering and Construction Management
John D. Baxter, P.E. Engineering and Construction Management

ab

TITLE: GASKINS ROAD EMBANKMENT REPAIR PROJECT

BID NO. JCF-0011-21 (PW)

OPEN DATE: OCTOBER 7, 2020 @ 2:00PM

BUYER: MARILYN LAIDLER

No. Invited: (13) No. Received (6 ) No Bids: (1 )

| ITEM | DESCRIPTION OF WORK | UNIT | EST.QTY | MOUNT TABOR CONSULTING, LLC UNIT COST | MOUNT TABOR CONSULTING, LLC TOTAL COST | HAGER CONSTRUCTION COMPANY UNIT COST | HAGER CONSTRUCTION COMPANY TOTAL COST | NICHOLAS CAIN CONSTRUCTION, LLC. UNIT COST | NICHOLAS CAIN CONSTRUCTION, LLC. TOTAL COST |
|---|---|---|---|---|---|---|---|---|---|
| 1 | MOBILIZATION, INCLUDES ONE PROJECT SIGN | LS | 1 | $ 26,646.40 | $ 26,646.40 | $ 65,989.00 | $ 65,989.00 | $ 75,000.00 | $ 75,000.00 |
| 2 | SITE PREPARATION | LS | 1 | $ 53,416.00 | $ 53,416.00 | $ 498,587.00 | $ 498,587.00 | $ 315,750.14 | $ 315,750.14 |
| 3 | MAINTENANCE OF TRAFFIC | LS | 1 | $ 7,150.00 | $ 7,150.00 | $ 12,588.00 | $ 12,588.00 | $ 14,375.72 | $ 14,375.72 |
| 4 | REGULAR EXCAVATION AND FILL | LS | 1 | $ 20,516.10 | $ 20,516.10 | $ 210,723.00 | $ 210,723.00 | $ 274,018.38 | $ 274,018.38 |
| 5 | OVEREXCAVATION (CONTINGENCY) | CY | 250 | $ 23.10 | $ 5,775.00 | $ 3.00 | $ 750.00 | $ 12.00 | $ 3,000.00 |
| 6 | A-3 SAND BACKFILL (CONTINGENCY) | CY | 250 | $ 30.80 | $ 7,700.00 | $ 6.00 | $ 1,500.00 | $ 26.15 | $ 6,537.50 |
| 7 | HAULING AND DISPOSAL OF UNSUITABLE MATERIALS (CONTINGENCY) | CY | 250 | $ 20.90 | $ 5,225.00 | $ 7.00 | $ 1,750.00 | $ 20.00 | $ 5,000.00 |
| 8 | 8 INCH CONCRETE DITCH PAVEMENT, INCLUDES WEEP HOLES | SY | 785 | $ 192.50 | $ 151,112.50 | $ 150.00 | $ 117,750.00 | $ 245.00 | $ 192,325.00 |
| 9 | RESET AND CONNECT EXISTING 48 INCH TO DITCH PAVEMENT | EA | 1 | $ 1,021.90 | $ 1,021.90 | $ 65,987.00 | $ 65,987.00 | $ 18,638.27 | $ 18,638.27 |
| 10 | GRASSING, COJ SPECIFICATION 145 | SY | 900 | $ 7.98 | $ 7,182.00 | $ 5.15 | $ 4,635.00 | $ 15.57 | $ 14,013.00 |
| 11 | DEWATERING | LS | 1 | $ 43,110.10 | $ 43,110.10 | $ 125,650.00 | $ 125,650.00 | $ 62,839.20 | $ 62,839.20 |
| 12 | EROSION CONTROL AND POLLUTION ABATEMENT | LS | 1 | $ 24,543.20 | $ 24,543.20 | $ 11,565.00 | $ 11,565.00 | $ 15,849.00 | $ 15,849.00 |
| | **TOTAL BID (ITEM NOS. 1-12)** | | | | **$ 353,398.20** | | **$ 1,117,474.00** | | **$ 997,346.21** |
| | **CONFLICT OF INTEREST:** | | | YES | | YES | | YES | |
| | **LICENSED SUBS:** | | | YES | | YES | | NONE LISTED | |
| | **ADDENDUM (S) ACKNOWLEDGED: (1,2 )** | | | YES | | YES | | YES | |

| TITLE: | GASKINS ROAD EMBANKMENT REPAIR PROJECT | | | BAKER CONSULTING & ENGINEERING LLC | | PARS CONSTRUCTION SERVICES, LLC | | ONAS CORPORATION | |
|---|---|---|---|---|---|---|---|---|---|
| BID NO. | JCF-0011-21 (PW) | | | | | | | | |
| OPEN DATE: | OCTOBER 7, 2020 @ 2:00PM | | | | | | | | |
| ITEM | DESCRIPTION OF WORK | UNIT | EST.QTY | UNIT COST | TOTAL COST | UNIT COST | TOTAL COST | UNIT COST | TOTAL COST |
| 1 | MOBILIZATION, INCLUDES ONE PROJECT SIGN | LS | 1 | $ 93,149.51 | $ 93,149.51 | $ 21,060.00 | $ 21,060.00 | $ 30,000.00 | $ 30,000.00 |
| 2 | SITE PREPARATION | LS | 1 | $ 306,852.79 | $ 306,852.79 | $ 78,000.00 | $ 78,000.00 | $ 55,000.00 | $ 55,000.00 |
| 3 | MAINTENANCE OF TRAFFIC | LS | 1 | $ 4,816.29 | $ 4,816.29 | $ 3,900.00 | $ 3,900.00 | $ 10,000.00 | $ 10,000.00 |
| 4 | REGULAR EXCAVATION AND FILL | LS | 1 | $ 172,523.82 | $ 172,523.82 | $ 23,400.00 | $ 23,400.00 | $ 31,000.00 | $ 31,000.00 |
| 5 | OVEREXCAVATION (CONTINGENCY) | CY | 250 | $ 14.38 | $ 3,595.00 | $ 30.00 | $ 7,500.00 | $ 10.00 | $ 2,500.00 |
| 6 | A-3 SAND BACKFILL (CONTINGENCY) | CY | 250 | $ 29.95 | $ 7,487.50 | $ 67.08 | $ 16,770.00 | $ 12.00 | $ 3,000.00 |
| 7 | HAULING AND DISPOSAL OF UNSUITABLE MATERIALS (CONTINGENCY) | CY | 250 | $ 23.96 | $ 5,990.00 | $ 30.00 | $ 7,500.00 | $ 15.00 | $ 3,750.00 |
| 8 | 8 INCH CONCRETE DITCH PAVEMENT, INCLUDES WEEP HOLES | SY | 785 | $ 281.55 | $ 221,016.75 | $ 124.80 | $ 97,968.00 | $ 85.00 | $ 66,725.00 |
| 9 | RESET AND CONNECT EXISTING 48 INCH TO DITCH PAVEMENT | EA | 1 | $ 7,188.49 | $ 7,188.49 | $ 17,784.00 | $ 17,784.00 | $ 3,500.00 | $ 3,500.00 |
| 10 | GRASSING, COJ SPECIFICATION 145 | SY | 900 | $ 11.98 | $ 10,782.00 | $ 4.45 | $ 4,005.00 | $ 10.00 | $ 9,000.00 |
| 11 | DEWATERING | LS | 1 | $ 68,290.68 | $ 68,290.68 | $ 31,200.00 | $ 31,200.00 | $ 12,000.00 | $ 12,000.00 |
| 12 | EROSION CONTROL AND POLLUTION ABATEMENT | LS | 1 | $ 10,303.51 | $ 10,303.51 | $ 39,000.00 | $ 39,000.00 | $ 10,000.00 | $ 10,000.00 |
| | TOTAL BID (ITEM NOS. 1-12) | | | $ | 911,996.34 | $ | 348,087.00 | $ | 236,475.00 |
| | CONFLICT OF INTEREST: | | | YES | | YES | | YES | |
| | LICENSED SUBS: | | | SELF-PERFORM | | SELF-PERFORM | | SELF-PERFORM | |
| | ADDENDUM (S) ACKNOWLEDGED: (1,2 ) | | | YES | | YES | | YES | |

**Department of Finance and Administration**
**Procurement Division**

# CITY OF JACKSONVILLE

October 13, 2020

**To:** Gregory A. Pease, Chief
Procurement Division

**From:** Aileen Cruz, Business Analyst AC
Jacksonville Small & Emerging Business Office (JSEB) & Contract Compliance Office

**Re:** **JCF-0011-21 – Gaskins Road Embankment Repair Project**

The Jacksonville Small & Emerging Business (JSEB) Office has reviewed the lowest bidder/proposer for compliance with the Jacksonville Small and Emerging Business (JSEB) program. Based upon the review, and the areas of certification, the lowest bidder/proposer is **ONAS Corporation**, with a bid of **$236,475.00** which meets the goal of utilizing **100%** JSEB.

Our review efforts are documented and available upon request. Please let us know if you have any questions or concerns. I can be reached at (904) 255-8828.

cc: Marilyn Laidler
Rose Nettles

214 N. Hogan Street, Suite 800 | Jacksonville, FL 32202 | Phone: 904.255.8840 | Fax: 904.255.8842 | www.jseb.coj.net

## GASKINS ROAD EMBANKMENT REPAIR PROJECT
## SECTION 3 PROPOSAL

**BID NO.: JCF-0011-21**

| Bid Item No. | Item Description | Unit | Est Qty | Unit Cost | Total Cost |
|---|---|---|---|---|---|
| 1 | MOBILIZATION, includes one project sign. | LS | 1 | | |
| 2 | SITE PREPARATION | LS | 1 | | |
| 3 | MAINTENANCE OF TRAFFIC | LS | 1 | | |
| 4 | REGULAR EXCAVATION AND FILL | LS | 1 | | |
| 5 | OVEREXCAVATION (CONTINGENCY) | CY | 250 | | |
| 6 | A-3 SAND BACKFILL (CONTINGENCY) | CY | 250 | | |
| 7 | HAULING AND DISPOSAL OF UNSUITABLE MATERIALS (CONTINGENCY) | CY | 250 | | |
| 8 | 8 INCH CONCRETE DITCH PAVEMENT, includes weep holes | SY | 785 | | |
| 9 | RESET AND CONNECT EXISTING 48 INCH TO DITCH PAVEMENT | EA | 1 | | |
| 10 | GRASSING, COJ SPECIFICATION 145 | SY | 900 | | |
| 11 | DEWATERING | LS | 1 | | |
| 12 | EROSION CONTROL AND POLLUTION ABATEMENT | LS | 1 | | |
| | | | | **TOTAL BID (ITEM NOS. 1-12):** | |

Enter on Page (3-1)

### B. BASIS OF AWARD

The project may be awarded to the lowest responsive, responsible Bidder contingent on the availability of funds within the project's approved budget. The Total Base Bid plus selected Alternate(s), if any, will be used to determine the lowest bidder. If selected, Alternate(s) will be awarded in the order listed (i.e. - 1,2,3…). The CITY has the right to reject any or all bids.

### C. REVISIONS OF BID PROPOSAL FORM

Request for revision of the Bid Proposal Form must be made to the ENGINEER at least ten (10) days prior to date of opening of Bids. Revision of the Bid Proposal by the Bidder will void the Bid.

### D. CONTRACT EXPIRATION DATE

The Contract expiration date shall be established as follows:

The notice to proceed date plus ten (10) calendar days for mobilization, plus the construction time established in the Proposal, plus time extensions pursuant to valid change orders (which shall establish the construction completion date), plus 120 days to assure a contract exists beyond the scheduled construction completion date in order to comply with Executive Order Number 2013-05.

GASKINS ROADS EMBANKMENT REPAIR
SECTION 30

SCOPE OF WORK

30.1 Scope The work covered by these plans and specifications consists of furnishing all labor, materials and equipment; and performing all operations necessary for the construction of GASKINS ROADS EMBANKMENT REPAIR, as specified in the Contract Documents.

30.2 Location This project is located within the limits a City of Jacksonville, Florida. The construction area is located on RE #014507-0015, 0 Fillyside Trail, adjacent to the Hannah Stables Subdivision.

30.3 Intent It is the intent of these Contract Documents to construct the GASKINS ROADS EMBANKMENT REPAIR as shown on the plans and including but not limited to:

1. Installation of Erosion Control items.
2. Site preparation.
3. Maintenance of Traffic
4. Concrete Ditch pavement installation.
5. Grassing

It is not the intent of these Contract Documents to minutely define the mode and fabric of construction of this project, but rather to set forth reasonable and rational criteria for the construction thereof.