6

SUBJECT: BERT MAXWELL DREDGING

BID #: CF-0144-21 **OPEN DATE: 2021-09-15**

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT: CONSTRUCTION FIXED- ENCOURAGEMENT

AGENCY: PUBLIC WORKS

BASIS OF AWARD: TOTAL BASE BID, PLUS SELECTED ALTERNATES (IF ANY)-LOWEST RESPONSIVE, RESPONSIBLE BIDDER

NUMBER OF BIDS INVITED: 5 **NUMBER RECEIVED: 2** **OTHER: 0**

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:
Recommend approval of award to Brance Diversified, Inc. as the lowest responsive, responsible bidder for the Bert Maxwell Dredging project with a total base bid amount of $641,620.00; Alternate 1 in the amount of $22,000.00; Alternate 2 in the amount of $22,840.00; Alternate 3 (Line 10 & 11) in the amount of $67,020.00 for a total award amount not to exceed $753,480.00.

Funding for this award shall be encumbered from 33101.167101.565050.002563.00000000.00000.0000000. To be executed by formal contract through the Office of General Counsel.

ATTACHMENTS: Recommendation Memo, Bid Tabulation, Basis of Award, Scope of Work

ANALYST: _____ BRYAN MATUS

RESPECTFULLY SUBMITTED: _____ GREGORY PEASE, CHIEF PROCUREMENT DIVISION

CONCURRENCE BY: Robin G. Smith P.E., Chief, Engineering & Construction Management

---

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

ACTION OF AWARDING AUTHORITY DATE _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

City of Jacksonville, Florida

Lenny Curry, Mayor

Department of Public Works
214 N. Hogan St., 10th floor
Jacksonville, FL 32202
(904) 255-8786
www.coj.net

ONE CITY ONE JACKSONVILLE

November 2, 2021

TO: Gregory W. Pease
Chief of Procurement

THRU: John P. Pappas, P.E.
Director

FROM: Robin G. Smith, P. E.
Chief, Engineering & Construction Management

Daryl T. Joseph
Director, Parks, Recreation and Community Services

SUBJECT: RECOMMENDATION TO AWARD

RE: Bert Maxwell Channel Dredging

Bid No.:	CF-0144-21
Bid Date:	September 15, 2021
Award Amount:	$753,480.00
Internal Services Account No.	PWEN011AD

The Department of Public Works has tabulated and reviewed the two (2) bids received on the referenced project for accuracy and compliance with the contract documents. The low bid is by Brance Diversified, Inc. The project was bid as encouragement. In addition, Public Works has confirmed through www.myfloridalicense.com the appropriate licenses for this contractor and listed subcontractors, if applicable.

We therefore recommend that award of the Total Base Bid and Bid Alternates 1, 2 and 3 for Bert Maxwell Channel Dredging be awarded to Brance Diversified, Inc., 601 Bryan Street, Jacksonville, FL 32202, in accordance with the attached bid documents in the amount of $753,480.00.

Funding for this project should be a follows:

ACCOUNTS:	TOTAL
33101.167101.565050.002563.00000000.00000.0000000	
002563	
PRSC Parks & Rec Capital Projects - Parks and Recreation	
565050	
2	
33101-381910-PRC00719	
$753,480.00	$753,480.00

RGS/lw

Attachments

cc: Lori West, Engineering and Construction Management
Robert Scott, P.E. Engineering and Construction Management

PQ- HORZIONTAL OR MARINE

TITLE: BERT MAXWELL CHANNEL DREDGING

BID NO. CF-0144-21 (PW)

OPEN DATE: SEPTEMBER 15, 2021@ 2:00PM

BUYER: MARILYN LAIDLER

No. Invited: (5) No. Received (2) No Bids: (0)

ITEM	DESCRIPTION OF WORK	UNIT	EST.QTY	BRANCE DIVERSIFIED UNIT COST	BRANCE DIVERSIFIED TOTAL COST	WATERFRONT PROPERTY SERVICES, LLC DBA GATOR DREDGING UNIT COST	WATERFRONT PROPERTY SERVICES, LLC DBA GATOR DREDGING TOTAL COST
1	MOBILIZATION/DEMOBILIZATION	LS	1	$ 50,000.00	$ 50,000.00	$ 580,000.00	$ 580,000.00
2	ENVIRONMENTAL PROTECTION AND EROSION CONTROL	LS	1	$ 10,000.00	$ 10,000.00	$ 5,000.00	$ 5,000.00
3	PRE- AND POST-DREDGE SURVEYS	LS	1	$ 20,000.00	$ 20,000.00	$ 12,000.00	$ 12,000.00
4	BASE DREDGING AND DEWATERING (CELLS 2 AND 7) (-6 FT NAVD88 MINUS 1-FT OVERDEPTH)	CY	1,142	$ 50.00	$ 57,100.00	$ 120.00	$ 137,040.00
5	BASE DREDGED MATERIAL TRANSPORT AND DISPOSL AT OFFSITE MUNICIPAL SOLID WASTE DISPOSAL FACILITY (CELLS 2 AND 7)	CY	1142	$ 50.00	$ 57,100.00	$ 20.00	$ 22,840.00
6	BASE DREDGING (CELLS 1 AND 3-6) (-6FT NAVD88 MINUS 1- FT OVERDEPTH)	CY	7457	$ 30.00	$ 223,710.00	$ 90.00	$ 671,130.00
7	BASE DREGED MATERIAL TRANSPORT AND DISPOSAL AT BARTRAM ISLAND (CELLS 1 AND 3-6)	CY	7457	$ 30.00	$ 223,710.00	$ 30.00	$ 223,710.00
	TOTAL BID (ITEM NOS. 1-7)			$	641,620.00	$	1,651,720.00
8	ALTERNATE 1- REPLACE CHANNEL MARKERS	EA	11	$ 2,000.00	$ 22,000.00	$ 4,000.00	$ 44,000.00
9	ALTERNATE 2- ADD FLOCCULANT/POLYMER TO DEWATERING PROCESS	CY	1142	$ 20.00	$ 22,840.00	$ 50.00	$ 57,100.00
10	ALTERNATE 3- ADDITIONAL DREDGING (-6FT NAVD88 MINUS 1-FT OVERDREGE)	CY	1117	$ 30.00	$ 33,510.00	$ 80.00	$ 89,360.00
11	ALTERNATE 3- ADDITIONAL DREDGED MATERIAL TRANSPORT AND DISPOSAL AT BARTRAM ISLAND	CY	1117	$ 30.00	$ 33,510.00	$ 30.00	$ 33,510.00
	BID ALTERNATE 1, 2, & 3 (ITEMS 8-11)			$	111,860.00	$	122,870.00
	CONFLICT OF INTEREST:			YES		YES	
	BID BOND:			YES		YES	
	LICENSED SUBS:			N/A		N.A	
	ADDENDUM (S) ACKNOWLEDGED: ( )						

B. **BASIS OF AWARD**

The project may be awarded to the lowest responsive, responsible Bidder contingent on the availability of funds within the project's approved budget. The Total Base Bid plus selected Alternate(s), if any, will be used to determine the lowest bidder. If selected, Alternate(s) will be awarded in the order listed (i.e. – 1,2,3...). The CITY has the right to reject any or all bids.

C. **REVISIONS OF BID PROPOSAL FORM**

Request for revision of the Bid Proposal Form must be made to the ENGINEER at least ten (10) days prior to date of opening of Bids. Revision of the Bid Proposal by the Bidder will void the Bid.

D. **CONTRACT EXPIRATION DATE**

The Contract expiration date shall be established as follows:

The notice to proceed date plus ten (10) calendar days for mobilization, plus the construction time established in the Proposal, plus time extensions pursuant to valid change orders (which shall establish the construction completion date), plus 120 days to assure a contract exists beyond the scheduled construction completion date in order to comply with Executive Order Number 2013-05.

E. **BID CHANGES**

No changes in the amount of Bids appearing on the outside of Bids will be considered. Only the amounts shown on bidding documents inside the envelope will be considered. All changes, corrections and erasures must be initialed by the person signing the bid.

F. **CONSTRUCTION COMPLETION**

The CONTRACTOR shall begin work within ten (10) calendar days, including Sundays and holidays, after the date of written notice from the Owner to begin work, and shall complete the Base Bid work within **180 calendar days** including Sundays and holidays, after the expiration of such ten (10) day notice. If the Bidder determines that "off-hours" work is anticipated to complete the project within such allotted times, a schedule therefore shall be attached to this proposal as required by Section 20.3.4 of the General Conditions.

G. **BID SECURITY**

If Bid Security is required for this project, a Certified Check on
_____ (or) Cashier's Check on
_____ (or) Bid Bond properly executed by the undersigned and by qualified surety in the sum of _____ representing not less than five percent (5%) of the total amount of Bid, made payable to the Tax Collector, City of Jacksonville, Florida, which the undersigned Bidder hereby deposits as a guarantee of good faith and which it agrees to forfeit to the CITY of Jacksonville, not as a penalty, but as fixed and liquidated damages in the event it fails to enter

BERT MAXWELL CHANNEL DREDGING

SECTION 30

SCOPE OF WORK

30.1 SCOPE

The work covered by these Specifications consists of furnishing all equipment and labor and performing all operations necessary for dredging of a channel in Bert Maxwell with a variable bottom width and 8H:1V side slopes; creating and maintaining a temporary dredged material management area; dewatering some of the dredged material; transporting and depositing some dredged material to an offsite municipal solid waste disposal facility and some dredged material to JAXPORT's Bartram Island dredged material management area; providing environmental protection and erosion control; and performing pre- and post-dredge surveys. All work shall be completed in accordance with this specification, Drawings and permits that are a part of these Contract Documents.

30.2 INTENT

These Contract Documents intend to provide the CITY with dredging and all other appurtenances necessary for completion of project. These Contract Documents do not intend to minutely define the mode, means, methods, techniques, sequence or procedures of construction selected by the CONTRACTOR, or the safety precautions and programs incident to the work of the CONTRACTOR, but rather to set forth reasonable and rational criteria for the construction thereof.

30.3 PROJECT LOCATION

The project locates in north Jacksonville near the Trout River.