SUBJECT: JFRD FIRE STATION APRON & DRIVEWAY REPAIR – FIRE STATIONS 31,34 & 36

BID #: CF-0097-23 **OPEN DATE:** June 21, 2023

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT: CONSTRUCTION CONTRACT – FROM EXECUTION OF CONTRACT THROUGH COMPLETION

AGENCY: PUBLIC WORKS

BASIS OF AWARD: ALL OR NONE TO THE LOWEST RESPONSIVE, RESPONSIBLE BIDDER

NUMBER OF BIDS INVITED: 30 **NUMBER RECEIVED:** 2 **OTHER:** 0

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:
Recommend approval of award to the lowest responsive, responsible bidder, Onas Corporation. Total expenditure not to exceed $287,575.00. Period of service will be from execution of contract through completion of the project.

Funding Source: 32111.153103.565051.010412.00000000.00000.0000000 – $ 3,004.16
32111.153101.565051.010412.00000000.00000.0000000 - $284,570.84
to be executed via formal contract through the Office of General Counsel

ATTACHMENTS: Recommendation Memo; Bid Tabulation, Scope of Work

ANALYST: _____
JACLYN STAMOS

RESPECTFULLY SUBMITTED: _____
DUSTIN FREEMAN, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: Robin Smith, Chief, Engineering and Construction Management Division, Public Works

---

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

ACTION OF AWARDING AUTHORITY DATE _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

City of Jacksonville, Florida

Donna Deegan, Mayor

Department of Public Works
214 N. Hogan St., 10th floor
Jacksonville, FL 32202
(904) 255-8786
www.coj.net

ONE CITY ONE JACKSONVILLE

July 05, 2023

TO: Dustin Freeman
Chief of Procurement

THRU: Steven D. Long, Jr., P.E.
Director of Public Works

FROM: Robin G. Smith, P. E.
Chief, Engineering & Construction Managements

Keith Powers
Director, Jacksonville Fire & Rescue

SUBJECT: RECOMMENDATION TO AWARD

RE: JFRD Fire Station Apron & Driveway Repair-Fire Stations Nos. 31, 34, &36

Bid No.:	CF-0097-23
Bid Date:	June 21, 2023
Award Amount:	$287,575.00

The Department of Public Works has tabulated and reviewed the Two (2) bids received on the referenced project for accuracy and compliance with the contract documents. The apparent low bid is by ONAS Corporation. The project was bid as encouragement. In addition, Public Works has confirmed through www.myfloridalicense.com the appropriate licenses for this contractor and listed subcontractors, if applicable.

Accordingly, we recommend that the Bid for JFRD Fire Station Apron & Driveway Repair-Fire Stations Nos. 31, 34, & 36 be awarded to ONAS Corporation, 2050 University Blvd N., Jacksonville, Florida 32211, in accordance with the attached bid documents in the amount of $287,575.00.

Funding for this project should be encumbered as follows:

ACCOUNTS:		TOTAL
32111.153101.565051.010412.00000000.00000.0000000	32124.153103.565051.010412.00000000.00000.0000000	
010412	010412	
PWCP Public Bldgs. Capital Projects (F5190)-Other General Government Services	PWCP Public Bldgs. Capital Projects (F5190)-Other General Government Services	
565051	565051	
2	2	
321111-384020	32124-384020	
$284,570.84	$3,004.16	$287,575.00

RGS/rc

Attachments

cc: Lori West, Engineering and Construction Management
Richard Cooper, Engineering and Construction Management
Daniel VanSickle, P.E. Engineering and Construction Management

TITLE: JFRD FIRE STATION APRON AND DRIVEWAY REPAIRS- FIRE STATION 31,34,36

BID NO.: CF-0097-23

OPEN DATE: JUNE 28, 2023 @ 2 P.M.

ANALYST: JACLYN STAMOS

No. Invited: (30) No. Received (2) No Bids: (0)

Recorded By: MELISSA PEIRCE Announcer: JOHN HERNADEZ

ITEM	DESCRIPTION	EST. QTY	UNIT	HAGAR CONSTRUCTION UNIT PRICE	HAGAR CONSTRUCTION EXTENDED TOTAL	ONAS CORPORATION UNIT PRICE	ONAS CORPORATION EXTENDED TOTAL
	FIRE STATION 31						
1	MOBILIZATION	1	LS	$ 7,890.00	$ 7,890.00	$ 5,000.00	$ 5,000.00
2	SITE PREPORATION	1	LS	$ 9,965.00	$ 9,965.00	$ 8,000.00	$ 8,000.00
3	MAINTENANCE OF TRAFFIC	1	LS	$ 4,125.00	$ 4,125.00	$ 2,000.00	$ 2,000.00
4	EROSION CONTROL AND POLLUTION ABATEMENT	1	LS	$ 7,245.00	$ 7,245.00	$ 2,800.00	$ 2,800.00
5	MILLING OF EXSITING ASPHALT (2.5" DEPTH)	1960	SY	$ 20.00	$ 39,200.00	$ 15.00	$ 29,400.00
6	SUPERPAVE ASPHALT CONCRETE (TYPE SP-12.5,2.5" LIFT)	270	TN	$ 275.00	$ 74,250.00	$ 200.00	$ 54,000.00
			TOTAL	$	142,675.00	$	101,200.00
	FIRE STATION 34						
1	MOBILIZATION	1	LS	$ 9,650.00	$ 9,650.00	$ 5,000.00	$ 5,000.00
2	SITE PREPORATION	1	LS	$ 12,450.00	$ 12,450.00	$ 18,000.00	$ 18,000.00
3	MAINTENANCE OF TRAFFIC	1	LS	$ 3,685.00	$ 3,685.00	$ 4,000.00	$ 4,000.00
4	EROSION CONTROL AND POLLUTION ABATEMENT	1	LS	$ 5,560.00	$ 5,560.00	$ 3,000.00	$ 3,000.00
5	DEWATERING	1	LS	$ 900.00	$ 900.00	$ 2,800.00	$ 2,800.00
6	REGULAR EXAVATION AND FILL	1	LS	$ 5,745.00	$ 5,745.00	$ 8,000.00	$ 8,000.00
7	OVEREXCAVATION	50	CY	$ 26.00	$ 1,300.00	$ 30.00	$ 1,500.00
8	A3 SAND BACKFILL	50	CY	$ 26.00	$ 1,300.00	$ 30.00	$ 1,500.00
9	HAULING AND DISPOSAL OF UNSUITABLE MATERIAL	50	CY	$ 50.00	$ 2,500.00	$ 30.00	$ 1,500.00
10	12" COMPACTED SUB-BASE (98% MAX DENSITY)	207	SY	$ 42.00	$ 8,694.00	$ 25.00	$ 5,175.00
11	8" CRUSHCRETE BASE COURSE (100% MAX DENSITY)	207	SY	$ 65.00	$ 13,455.00	$ 50.00	$ 10,350.00
12	8" CONCRETE DRIVEWAY, REINFORCES WITH #5 REBAR SPACED @ 12" oc ew	148	SY	$ 210.00	$ 31,080.00	$ 160.00	$ 23,680.00
13	8" CONCRETE DRIVEWAY REINFORCESD WITH FIBERMESH	60	SY	$ 215.00	$ 12,900.00	$ 150.00	$ 9,000.00
14	CITY STANDARD CURB & GUTTER (4,000 psi) COJ PLATE	31	LF	$ 100.00	$ 3,100.00	$ 60.00	$ 1,860.00
15	SODDING, COJ PLATE 145	7	SY	$ 50.00	$ 350.00	$ 20.00	$ 140.00
			TOTAL	$	112,669.00	$	93,505.00
	FIRE STATION 36						
1	MOBILIZATION	1	LS	$ 15,250.00	$ 15,250.00	$ 5,000.00	$ 5,000.00
2	SITE PREPORATION	1	LS	$ 26,000.00	$ 26,000.00	$ 8,000.00	$ 8,000.00
3	MAINTENANCE OF TRAFFIC	1	LS	$ 1,200.00	$ 1,200.00	$ 2,000.00	$ 2,000.00
4	EROSION CONTROL AND POLLUTION ABATEMENT	1	LS	$ 6,800.00	$ 6,800.00	$ 1,000.00	$ 1,000.00
5	DEWATERING	1	LS	$ 900.00	$ 900.00	$ 800.00	$ 800.00
6	REGULAR EXCAVATION AND FILL	1	LS	$ 7,850.00	$ 7,850.00	$ 5,000.00	$ 5,000.00
7	OVEREXCAVATION	50	CY	$ 26.00	$ 1,300.00	$ 30.00	$ 1,500.00
8	A3 SAND BACKFILL	50	CY	$ 26.00	$ 1,300.00	$ 30.00	$ 1,500.00
9	HAULING AND DISPOSAL OF UNSUITABLE MATERIAL	50	CY	$ 125.00	$ 6,250.00	$ 30.00	$ 1,500.00
10	MILLING OF EXSITING ASPHALT (1" DEPTH)	500	SY	$ 21.00	$ 10,500.00	$ 15.00	$ 7,500.00
11	SUPERPAVE ASPHALT CONCRETE (TYPE SP-9.5,5, 1" LIFT)	TN	28	$ 615.00	$ 17,220.00	$ 250.00	$ 7,000.00
12	12" COMPACTED SUB-BASE (98% MAX DENSITY)	138	SY	$ 105.00	$ 14,490.00	$ 25.00	$ 3,450.00
13	6" RECLAIMED ASPHALT PAVEMENT (rap) BASE (95% MAX DENSITY	138	SY	$ 105.00	$ 14,490.00	$ 150.00	$ 20,700.00
14	6" CONCRETE DRIVEWAY NON REINFORCED	138	SY	$ 215.00	$ 29,670.00	$ 150.00	$ 20,700.00
15	CITY STD DROP CURB (4000 PSI) COJ PLATE P-301	121	LF	$ 100.00	$ 12,100.00	$ 40.00	$ 4,840.00
16	SODDING	19	SY	$ 50.00	$ 950.00	$ 20.00	$ 380.00
			TOTAL	$	166,270.00	$	90,870.00
			GRAND TOTAL	$	421,614.00	$	287,575.00
			CONFLICT OF INTEREST:	Y		Y	
			BID FORM	Y		Y	
			EX OFFENDERS FORM	N		Y	
			ADDENDUM(1):	Y		Y	

JFRD FIRE STATION APRON & DRIVEWAY REPAIRS –
FIRE STATIONS Nos. 31, 34 & 36
SECTION 30

SCOPE OF WORK

30.1 Scope: The work covered by these plans and specifications consists of furnishing all labor, materials and equipment; and performing all operations necessary for the construction of **JFRD FIRE STATION APRON & DRIVEWAY REPAIRS – FIRE STATIONS Nos. 31, 34 & 36**, as specified in the Contract Documents.

30.2 Location: This project is located within the limits of the City of Jacksonville, Florida right of way. The construction areas are located at the following JFRD Fire Stations:

Fire Station No.	Address	Real Estate #
31	5527 HILLMAN DR.	014509-0520
34	11248 ROSS BLVD.	019830-0000
36	2926 LIPPIA RD.	028598-0000

30.3 Intent: It is the intent of these Contract Documents to construct the **JFRD FIRE STATION APRON & DRIVEWAY REPAIRS – FIRE STATIONS Nos. 31, 34 & 36** as shown on the plans and including but not limited to:

1. Erosion Control Installation and Maintenance
2. Temporary Traffic Control
3. Existing Concrete Removal
4. Existing Asphalt Milling
5. Super-Duty Concrete Driveway Construction
6. Heavy-Duty Concrete Driveway Construction
7. Asphalt Resurfacing
8. City Standard Curb & Gutter and Drop Curb Construction
9. Grassing Installation per COJ Spec. 145 in all disturbed areas.

It is not the intent of these Contract Documents to minutely define the mode and fabric of construction of this project, but rather to set forth reasonable and rational criteria for the construction thereof.